

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S-84 P.A. 224	04-00137-02-FP	HENRY	23	2
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT 5N-224(168)	

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: I000-2A

CODE NO.	ITEM	UNIT	TOTAL
* 20200410	EARTH EXCAVATION (SPECIAL)	CU YD	1,463
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100
20400800	FURNISHED EXCAVATION	CU YD	2,894
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	243
25000500	PHOSPHUROUS FERTILIZER NUTRIENT	POUND	243
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	243
25000200	SEEDING, CLASS 2	ACRE	2.69
25100115	MULCH METHOD 2	ACRE	2.69
25100630	EROSION CONTROL BLANKET	SQ YD	167
28000300	TEMPORARY DITCH CHECK	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	908
* 31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1,911
* 35100100	AGGREGATE BASE COURSE, TYPE A	TON	955
* 40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30
* 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,146
* 40600300	AGGREGATE PRIME COAT	TON	15
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	245
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,426
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	1,426
* 542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	112
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	22
67100100	MOBILIZATION	L SUM	1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	476
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	158
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	170
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,201
Δ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,312
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	296
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	131
X3550010	BITUMINOUS BASE COURSE SUPERPAVE	TON	1,132
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1,102
* Z0005400	BREAKER-RUN CRUSHED STONE	TON	205

Δ SPECIALTY ITEMS