

| | | | | |
|-----------------------|----------------|-----------|-----------------------------|-----------|
| ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| S-84 F.A. 224 | 04-00137-02-FP | HENRY | 23 | 5 |
| FED. ROAD DIST. NO. 7 | | ILL. ENDS | FED. AID PROJECT SP-2241061 | |

SCHEDULES

GENERAL NOTES

THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKS, SECTION OR SUBSECTION MONUMENTS ENCOUNTERED, UNTIL AN OWNER OR AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. ANY PROPERTY MARKS, SECTION OR SUBSECTION MONUMENTS UNLESS REFERENCED, DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.

THE CONTRACTOR SHALL REMOVE ALL STRUCTURES WITHIN THE EXISTING AND NEW RIGHT OF WAY AS DIRECTED BY THE ENGINEER AND AS SHOWN ON PLANS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED. ALL EXISTING DRAINAGE PIPES AND END SECTIONS SHALL BE CAREFULLY REMOVED DURING CONSTRUCTION AND STACKED ALONG THE RIGHT OF WAY AS DIRECTED BY THE ENGINEER. THIS SALVAGE AND STORAGE OF EXISTING DRAINAGE PIPES AND END SECTIONS SHALL BE CONSIDERED AN INCIDENTAL ITEM AND WILL NOT BE PAID FOR SEPARATELY. ALL SALVAGED PIPES SHALL REMAIN THE PROPERTY OF THE COUNTY.

ALL TELEPHONE AND ELECTRIC POLES, GAS PIPES, ETC. IN THE WAY OF THE IMPROVEMENT SHALL BE MOVED BY THE UTILITIES PRIOR TO CONSTRUCTION AND SHALL NOT BE INCLUDED IN THE CONTRACT. THE CONTRACTOR SHALL NOTIFY THE RESPECTIVE UTILITIES TO MAKE THE NECESSARY ADJUSTMENTS PRIOR TO THIS CONSTRUCTION.

THE LOCATION AND ELEVATION OF THE VARIOUS UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE NOT TO BE TAKEN AS EXACT. THE CONTRACTOR SHALL USE SPECIAL CARE WHEN CONDUCTING CONSTRUCTION OPERATIONS NEAR THEM TO PREVENT DAMAGE.

ALL TREES LESS THAN 6" DIAMETER WITHIN THE CONSTRUCTION LINES AND SHOWN ON THE PLANS TO BE REMOVED WILL NOT BE PAID FOR UNDER THE BID ITEM OF "TREE REMOVAL". THE COST OF REMOVING THESE TREES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID PER CUBIC YARD FOR EARTH EXCAVATION (SPECIAL).

THE FINAL TOP 4" OF SOIL IN ANY AREA DISTURBED BY THE CONTRACTOR MUST BE ABLE TO SUPPORT VEGETATION.

EXISTING MAIL BOXES, STREET SIGNS AND TRAFFIC SIGNS THAT ARE WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED AND RESET BY THE CONTRACTOR. COST OF REMOVING AND RESETTING TO BE INCLUDED IN THE CONTRACT UNIT PRICE BID PER UNIT FOR EARTH EXCAVATION (SPECIAL)

WHERE THE PROPOSED CONSTRUCTION MEETS AN EXISTING BITUMINOUS SURFACE, OR WHERE SAWING IS STATED ON THE PLANS, THE EXISTING SURFACE SHALL BE SAWED IN A NEAT, STRAIGHT LINE. COST OF SAWING TO BE INCLUDED IN THE CONTRACT UNIT PRICE PER UNIT FOR EARTH EXCAVATION (SPECIAL).

EARTHWORK SCHEDULE

| LOCATION | EARTH EXCAVATION (SPECIAL) | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% | EMBANKMENT | EARTHWORK BALANCE WASTE (+) OR Shortage (-) |
|--|----------------------------|---|--------------|---|
| WOLF ROAD STA. 635+98.67 TO 655+68.87 | 1,264 | 948 | 3,634 | -2,686 |
| HAZEL ROAD STA. 500+00 TO 504+75 | 199 | 149 | 357 | -208 |
| TOTALS | 1,463 | 1,097 | 3,991 | -2,894 |

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

| STATION | CU YD | REMARKS |
|----------------------|------------|-----------------------------|
| CONTINGENCY ITEM | 100 | AS DIRECTED BY THE ENGINEER |
| PROJECT TOTAL | 100 | |

20201200

NITROGEN FERTILIZER

| STATION | POUNDS | REMARKS |
|------------------------------------|------------|--------------------------|
| Wolf Rd. 635+98.67 - 655+68.87 | 176 | 1.95 ACRES @ 90 LBS/ACRE |
| 1200 E. Rd. 13+72.16 - 22+04.11 | 67 | .74 ACRES @ 90 LBS/ACRE |
| PROJECT TOTAL | 243 | |

25000400

PHOSPHOROUS FERTILIZER

| STATION | POUNDS | REMARKS |
|------------------------------------|------------|--------------------------|
| Wolf Rd. 635+98.67 - 655+68.87 | 176 | 1.95 ACRES @ 90 LBS/ACRE |
| 1200 E. Rd. 13+72.16 - 22+04.11 | 67 | .74 ACRES @ 90 LBS/ACRE |
| PROJECT TOTAL | 243 | |

25000500

POTASSIUM FERTILIZER

| STATION | POUNDS | REMARKS |
|------------------------------------|------------|--------------------------|
| Wolf Rd. 635+98.67 - 655+68.87 | 176 | 1.95 ACRES @ 90 LBS/ACRE |
| 1200 E. Rd. 13+72.16 - 22+04.11 | 67 | .74 ACRES @ 90 LBS/ACRE |
| PROJECT TOTAL | 243 | |

25000600

SEEDING, CLASS 2

| STATION | ACRES | REMARKS |
|------------------------------------|-------------|--------------|
| Wolf Rd. 635+98.67 - 655+68.87 | 1.95 | WOLF RD |
| 1200 E. Rd. 13+72.16 - 22+04.11 | 0.74 | 1200 E. ROAD |
| PROJECT TOTAL | 2.69 | |

25000200

MULCH METHOD 2

| STATION | ACRES | REMARKS |
|------------------------------------|-------------|--------------|
| Wolf Rd. 635+98.67 - 655+68.87 | 1.95 | WOLF RD |
| 1200 E. Rd. 13+72.16 - 22+04.11 | 0.74 | 1200 E. ROAD |
| PROJECT TOTAL | 2.69 | |

25100115

EROSION CONTROL BLANKET

| STATION | SQ YD | REMARKS |
|----------------------|------------|---------|
| R 653+00 - 655+50 | 167 | 6' WIDE |
| PROJECT TOTAL | 167 | |

25100630

TEMPORARY DITCH CHECK

| STATION | EACH | REMARKS |
|----------------------|----------|-----------------------------|
| L & R 636+00 | 2 | AS DIRECTED BY THE ENGINEER |
| R 648+00 | 1 | AS DIRECTED BY THE ENGINEER |
| L 648+50 | 1 | AS DIRECTED BY THE ENGINEER |
| L & R 655+50 | 2 | AS DIRECTED BY THE ENGINEER |
| PROJECT TOTAL | 6 | |

28000300

PERIMETER EROSION BARRIER

| STATION | FOOT | REMARKS |
|----------------------|------------|-------------------------------|
| R 636+00 - 639+00 | 300 | SET INSIDE EXIST. R.O.W. LINE |
| R 639+00 - 645+08 | 608 | SET INSIDE PROP. R.O.W. LINE |
| PROJECT TOTAL | 908 | |

28000400

SUB-BASE GRANULAR MATERIAL, TYPE B

| STATION | TONS | REMARKS |
|-------------------------------------|--------------|---------|
| Wolf Rd. L 635+98.67 - 645+78.46 | 317 | 8" |
| R 635+98.67 - 645+78.46 | 532 | 8" |
| L 645+78.46 - 655+68.87 | 565 | 8" |
| R 645+78.46 - 655+68.87 | 344 | 8" |
| 1200 E. Road L 13+72 - 15+71.34 | 67 | 8" |
| R 13+72 - 15+71.34 | 24 | 8" |
| L 20+19 - 22+04.11 | 16 | 8" |
| R 20+19 - 22+04.11 | 46 | 8" |
| PROJECT TOTAL | 1,911 | |

31101000

AGGREGATE SURFACE COURSE, TYPE B

| STATION | TONS | REMARKS |
|----------------------|-----------|------------------------------------|
| AS NEEDED BY ENGR. | 30 | CONTINGENCY ITEM FOR TEMP. ENTRYS. |
| PROJECT TOTAL | 30 | |

40200800