

SCHEDULES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S-94- F.A. 224	04-00137-02-FP	HENRY	23	6
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO. H11091	

AGGREGATE BASE COURSE, TYPE A		
STATION	TONS	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	159	4"
R 635+98.67 - 645+78.46	266	4"
L 645+78.46 - 655+68.87	283	4"
R 645+78.46 - 655+68.87	172	4"
1200 E. Road		
L 13+72 - 15+71.34	33	4"
R 13+72 - 15+71.34	12	4"
L 20+19 - 22+04.11	8	4"
R 20+19 - 22+04.11	23	4"
FEL 21+25	62	10"
FER 21+25	62	10"
PROJECT TOTAL	955	

35100100

BITUMINOUS MATERIALS (PRIME COAT)		
STATION	GALLONS	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	348	.5 GAL/SY ON AGGR
R 635+98.67 - 645+78.46	584	.5 GAL/SY ON AGGR
L 645+78.46 - 655+68.87	621	.5 GAL/SY ON AGGR
R 645+78.46 - 655+68.87	378	.5 GAL/SY ON AGGR
L 635+98.67 - 645+78.46	189	.1 GAL/SY SURFACING OVER BIT
R 635+98.67 - 645+78.46	249	.1 GAL/SY SURFACING OVER BIT
L 645+78.46 - 655+68.87	254	.1 GAL/SY SURFACING OVER BIT
R 645+78.46 - 655+68.87	195	.1 GAL/SY SURFACING OVER BIT
1200 E. Rd.		
L 13+72.16 - 13+72.16	73	.5 GAL/SY ON AGGR
R 13+72.16 - 13+72.16	26	.5 GAL/SY ON AGGR
L 20+19 - 22+04.11	18	.5 GAL/SY ON AGGR
R 20+19 - 22+04.11	50	.5 GAL/SY ON AGGR
L 13+72.16 - 13+72.16	40	.1 GAL/SY SURFACING OVER BIT
R 13+72.16 - 13+72.16	43	.1 GAL/SY SURFACING OVER BIT
L 20+19 - 22+04.11	41	.1 GAL/SY SURFACING OVER BIT
R 20+19 - 22+04.11	39	.1 GAL/SY SURFACING OVER BIT
PROJECT TOTAL	3,146	

40600100

AGGREGATE PRIME COAT		
STATION	TONS	REMARKS
ENTIRE PROJECT		
	15	3 LBS./S.Y.
PROJECT TOTAL	15	

40600300

BITUMINOUS BASE COURSE SUPERPAVE		
STATION	TONS	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	188	4.5"
R 635+98.67 - 645+78.46	315	4.5"
L 645+78.46 - 655+68.87	335	4.5"
R 645+78.46 - 655+68.87	204	4.5"
1200 E. Road		
L 13+72 - 15+71.34	39	4.5"
R 13+72 - 15+71.34	14	4.5"
L 20+19 - 22+04.11	10	4.5"
R 20+19 - 22+04.11	27	4.5"
PROJECT TOTAL	1,132	

X3550010

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50		
STATION	TONS	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	199	1 1/2" PLUS LEVELING
R 635+98.67 - 645+78.46	261	1 1/2" PLUS LEVELING
L 645+78.46 - 655+68.87	267	1 1/2" PLUS LEVELING
R 645+78.46 - 655+68.87	204	1 1/2" PLUS LEVELING
1200 E. Rd.		
L 13+72.16 - 13+72.16	42	1 1/2" PLUS LEVELING
R 13+72.16 - 13+72.16	45	1 1/2" PLUS LEVELING
L 20+19 - 22+04.11	43	1 1/2" PLUS LEVELING
R 20+19 - 22+04.11	41	1 1/2" PLUS LEVELING
PROJECT TOTAL	1,102	

X4066414

BITUMINOUS SURFACE REMOVAL - BUTT JOINT		
STATION	SQ YD	REMARKS
Wolf Rd.		
635+98.67 - 636+23.67	67	
655+43.57 - 655+68.87	67	
1200 E. Rd.		
13+72.16 - 13+97.16	51	
21+79.11 - 22+04.11	60	
PROJECT TOTAL	245	

40600980

STRIP REFLECTIVE CRACK CONTROL TREATMENT		
STATION	FOOT	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	919	2' WIDE APPLIED ALONG WIDENING
R 635+98.67 - 645+78.46	927	2' WIDE APPLIED ALONG WIDENING
L 645+78.46 - 655+68.87	958	2' WIDE APPLIED ALONG WIDENING
R 645+78.46 - 655+68.87	953	2' WIDE APPLIED ALONG WIDENING
1200 E. Rd.		
L 13+72.16 - 13+72.16	174	2' WIDE APPLIED ALONG WIDENING
R 13+72.16 - 13+72.16	174	2' WIDE APPLIED ALONG WIDENING
L 20+19 - 22+04.11	165	2' WIDE APPLIED ALONG WIDENING
R 20+19 - 22+04.11	156	2' WIDE APPLIED ALONG WIDENING
PROJECT TOTAL	4,426	

44300200

BITUMINOUS SHOULDERS SUPERPAVE		
STATION	TON	REMARKS
Wolf Rd.		
L 635+98.67 - 645+78.46	335	8', 4' & VAR
R 635+98.67 - 645+78.46	290	8', 4' & VAR
L 645+78.46 - 655+68.87	283	8', 4' & VAR
R 645+78.46 - 655+68.87	330	8', 4' & VAR
1200 E. Rd.		
L 13+72.16 - 13+72.16	44	8', 4' & VAR
R 13+72.16 - 13+72.16	56	8', 4' & VAR
L 20+19 - 22+04.11	52	8', 4' & VAR
R 20+19 - 22+04.11	37	8', 4' & VAR
PROJECT TOTAL	1,426	

48200200

PIPE CULVERTS, CLASS D, TYPE 1 15"		
STATION	EACH	REMARKS
FEL 21+25		
	56	
FER 21+25		
	56	
PROJECT TOTAL	112	

54200220

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
Wolf Rd.		
635+98.67 - 655+68.87	394	4-40 CL MARKING - 2 LIFTS
1200 E. Rd.		
13+72.16 - 15+46	40	4-40 CL MARKING - 2 LIFTS
20+00 - 22+04.11	42	4-40 CL MARKING - 2 LIFTS
PROJECT TOTAL	476	

70300100