

Contract 89393

SUMMARY OF QUANTITIES				TAZEWELL COUNTY	
				CONSTRUCTION TYPE CODE	
				ROADWAY	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1 000-2A	
20200100	EARTH EXCAVATION	CU YD	567	567	
20800150	TRENCH BACKFILL	CU YD	3	3	
* 25000210	SEEDING, CLASS 2A	ACRE	0.40	0.40	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36	
* 25100105	MULCH, METHOD 1	ACRE	0.40	0.40	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
20800510	INLET FILTERS	EACH	3	3	
28100125	STONE RIPRAP, CLASS B3	SQ YD	20	20	
28200200	FILTER FABRIC	SQ YD	20	20	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1,071	1,071	
40600200	BITUMINOUS MATERIALS (PRIMECOAT)	TON	3.3	3.3	
40600300	AGGREGATE (PRIMECOAT)	TON	6.0	6.0	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3,202	3,202	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13	13	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	1,172	1,172	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,166	1,166	
54010103	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	8	8	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54248515	CONCRETE COLLAR	EACH	1	1	
550A0050	STORM SEWER, CLASS A, TYPE 1 12"	FOOT	98	98	
60241800	INLETS, TYPE G-1	EACH	3	3	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	841	841	
67100100	MOBILIZATION	L SUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	233	233	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	70	70	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47	
* 78001110	PAINT PAVEMENT MARKING LINE - 4"	FOOT	5,064	5,064	
* 78001140	PAINT PAVEMENT MARKING LINE - 8"	FOOT	225	225	
* 78001150	PAINT PAVEMENT MARKING LINE - 12"	FOOT	165	165	

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				TAZEWELL COUNTY	
				CONSTRUCTION TYPE CODE	
				ROADWAY	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1 000-2A	
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	6	6	
X0320547	REMOVE AND REINSTALL END SECTION	EACH	1	1	
X0322996	END SECTIONS TO BE RELOCATED	EACH	1	1	
X4066524	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MULTY N50	TON	362	362	
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	80	80	
XX002804	STORM SEWERS, PVC 12" (SPECIAL)	FOOT	6	6	
XX004093	CONCRETE SLOPEWALL REMOVAL	SQ FT	170	170	
XX005347	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE N50	TON	270	270	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	



NORTH MAIN STREET IMPROVEMENT SUMMARY OF QUANTITIES

SURVEY	CHECKED	ISSUE DATE
DESIGN	APPROVED	02-21-08
REW	PRELIM. DATE	
DRAWN	DLC	PROJECT NO. ILS00003

SHEET  
**3**  
OF  
**20**