

# SCHEDULE OF QUANTITIES

CONTRACT NO. 91337

Remove & Replace Flagstone Wall #5000774	
Location	Foot
20+16.9 to 104+69.8, Rt.	46.0
<b>Total=</b>	<b>46.0</b>

Curb Removal 44000300	
Location	Feet
103+17.5 to 103+92.5, Lt.	76.0
104+56.1 to 104+73.1, Lt.	17.0
104+51.9 to 105+51.9, Rt.	103.7
103+65.2 to 103+89.4 Rt.	25.3
<b>Total=</b>	<b>222.0</b>

Inlets, Type A, Type 3 Frame and Grate 60235700	
Location	Each
21+22.0, 22.5' Lt.	1.0
103+82.8, 26.0' Rt.	1.0
<b>Total=</b>	<b>2.0</b>

Valve Boxes to be Adjusted 60266600	
Location	Each
104+62.8, 21.4' Rt.	1.0
20+43.9, 27.8' Rt.	1.0
<b>Total=</b>	<b>2.0</b>

Sodding 25200100	
Location	Sq. Yd.
NW Quadrant	54.0
NE Quadrant	44.0
SE Quadrant	101.0
SW Quadrant	76.0
<b>Total=</b>	<b>275.0</b>

Detectable Warnings 42400800	
Location	Sq. Ft.
NW Quadrant	23.2
NE Quadrant	20.0
SE Quadrant	18.0
SW Quadrant	26.8
<b>Total=</b>	<b>88.0</b>

Remove Junction Box XX003079	
Location	Each
104+59.1, 17.8' Lt.	1.0
105+21.8, 18.6' Rt.	1.0
<b>Total=</b>	<b>2.0</b>

Comb. Curb and Gutter Removal 44000500	
Location	Feet
21+19.0 to 21+48.0, Lt.	28.8
21+23.6 to 21+48.0, Rt.	24.4
21+19.6, Rt. to 104+55.6, Lt.	25.0
20+27.3 to 20+46.6, Rt.	19.3
105+51.9 to 105+84.4, Rt.	32.5
19+95.0 to 20+57.8, Lt.	65.0
<b>Total=</b>	<b>195.0</b>

Inlets, Type B, Type 3 Frame and Grate 60240220	
Location	Each
103+20.3, 19.7' Lt.	1.0
<b>Total=</b>	<b>1.0</b>

Removal of Existing Lighting Unit, Salvage 84200500	
Location	Each
104+58.5, 22.0' Lt.	1.0
105+24.2, 20.3' Rt.	1.0
<b>Total=</b>	<b>2.0</b>

Supplemental Watering 25200200	
Location	Unit
NW Quadrant	0.8
NE Quadrant	0.6
SE Quadrant	1.5
SW Quadrant	1.1
<b>Total=</b>	<b>4.0</b>

Comb. Conc. Curb & Gutter, Type B-6.18 60604400	
Location	Foot
20+46.6 Rt. 105+84.4 Rt.	147.0
21+48.0 Rt. 104+73.1 Lt.	64.2
103+19.4 Lt. 21+48.0 Lt.	116.4
103+65.2 Rt. 103+75.0 Rt.	9.4
<b>Total=</b>	<b>337.0</b>

Sign Removal X0974300	
Location	Each
21+29.7, 22.5' Lt.	1.0
104+57.7, 18.4' Lt.	1.0
105+30.4, 17.7' Rt.	1.0
20+40.8, 25.0' Rt.	1.0
103+80.3, 27.4' Rt.	1.0
<b>Total=</b>	<b>5.0</b>

Sidewalk Removal 44000600	
Location	Sq. Ft.
NW Quadrant	595.4
NE Quadrant	451.0
SE Quadrant	279.0
105+07.7 to 105+47.8, Rt.	91.6
SW Quadrant	518.0
<b>Total=</b>	<b>1935.0</b>

Manholes to be Adjusted 60255500	
Location	Each
103+83.5, 29.4' Lt.	1.0
<b>Total=</b>	<b>1.0</b>

Removal of Existing Lighting Unit, No Salvage 84200600	
Location	Foot
21+25.5, 22.9' Rt.	1.0
20+22.4, 22.2' Lt.	1.0
<b>Total=</b>	<b>2.0</b>

P. C. Concrete Base Course, 8" 35300300	
Location	Sq. Yd.
103+17.5 103+24.2 Lt.	1.6
103+80.6 21+27.0 Lt.	9.4
21+34.5 Rt. 104+65.4 Lt.	21.8
20+46.6 105+68.2 Rt.	52.5
103+75.0 Rt. 20+14.5 Lt.	28.7
<b>Total=</b>	<b>114.0</b>

Comb. Conc. Curb & Gutter, Type B-6.24 60605000	
Location	Foot
19+95.5 20+63.0 Lt.	77.7
20+27.3 20+46.6	19.3
<b>Total=</b>	<b>97.0</b>

Tree Removal (6-15 Units Dia.) 20100110	
Location	Inch Dia
104+69.4, 22.6' Lt.	6.0
<b>Total=</b>	<b>6.0</b>

Concrete Retaining Wall Removal 50104600	
Location	Feet
103+82.7 to 103+93.0 Lt.	10.3
21+16.5 to 21+34.2 Lt.	17.7
<b>Total=</b>	<b>28.0</b>

Inlets to be Adjusted with New Type 1 Frame openLid 60260300	
Location	Each
21+18.4, 21.2' Lt.	1.0
21+09.7, 23.4' Rt.	1.0
20+56.4, 27.5' Rt.	1.0
20+57.5, 31.1' Lt.	1.0
<b>Total=</b>	<b>4.0</b>

Lighting Foundation Removal 84200700	
Location	Each
21+25.5, 22.9' Rt.	1.0
20+22.4, 22.2' Lt.	1.0
<b>Total=</b>	<b>2.0</b>

Aggregate Surface Course, Ty. B 40200900	
Location	Cu Yd
NW Quadrant	5.0
<b>Total=</b>	<b>5.0</b>

P. C. Concrete Sidewalk Curb Z0042300	
Location	Foot
21+26.6 to 21+34.1, 28.3 - 30.6' Lt.	8.0
<b>Total=</b>	<b>8.0</b>

Pavement Removal 44000100	
Location	Sq. Yd.
103+17.5 to 21+34.5 Lt.	37.4
21+19.6 to 21+23.6, Rt.	0.9
104+55.4 to 104+73.1, Lt.	3.3
20+27.3 to 105+51.9, Rt.	22.0
106+65.2, Rt. to 19+95.0, Lt.	8.4
<b>Total=</b>	<b>72.0</b>

Storm Sewer, Class B Type1, 8" 550B0030	
Location	Feet
21+19.3 to 21+21.1, 21.9' Lt.	2.0
103+83.9 to 103+89.6, 26.5' Rt.	6.0
<b>Total=</b>	<b>8.0</b>

Valve Vault to be Adjusted 60265700	
Location	Each
103+89.3, 25.4' Lt.	1.0
<b>Total=</b>	<b>1.0</b>

Remove Electric Cable from Conduit 89502300	
Location	Foot
104+59.5 to 105+95.3, Lt.	135.8
105+22.2 to 106+66.4, Rt.	144.2
<b>Total=</b>	<b>280.0</b>

P.C. Concrete Sidewalk, 6" 42400300	
Location	Sq. Ft.
NW Quadrant	543.4
NE Quadrant	287.3
105+27.8, Rt.	27.8
SE Quadrant	300.3
SW Quadrant	484.2
<b>Total=</b>	<b>1643.0</b>