

# SUMMARY OF QUANTITIES



CITY OF URBANA  
PUBLIC WORKS  
ENGINEERING DIVISION

DRAWN BY: PLS  
CHECKED BY: GLJ  
DESIGNED BY: CES  
CITY SECTION  
95-00305-01-PV

Philo Road Improvements  
Summary of Quantities

SHEET NO.  
4  
OF  
62

SUMMARY OF QUANTITIES		SAFETY CODE		2A
		CONSTRUCTION CODE		1000
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 50% CITY
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3
* 60258300	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1
60258800	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 8 GRATE	EACH	1	1
* 60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2	2
60261000	INLETS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	2	2
* 60500060	REMOVING INLETS	EACH	13	13
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7209	7209
* 66700095	PERMANENT SURVEY MARKERS	EACH	2	2
* 67100100	MOBILIZATION	L SUM	1	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2425	2425
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1020	1020
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	900	900
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	671	671
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9068	9068
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	460	460
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	83	83
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30	30
* X0301232	SURVEY MARKER VAULT	EACH	2	2
* X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	132	132
* X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	451	451
* X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	1444	1444
* X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	3310	3310
* X6020125	RESTRICTED DEPTH INLET TYPE B, TYPE 3 FRAME AND GRATE	EACH	25	25

\* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES		SAFETY CODE		2A
		CONSTRUCTION CODE		1000
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 50% CITY
* XX000405	BUTT JOINTS, SPECIAL	SQ YD	226	226
* XX003330	MANHOLE TO BE ADJUSTED W/NEW TYPE 1 SEALED LID	EACH	1	1
* XX005483	RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, OPEN LID	EACH	2	2
* XX006432	AGGREGATE SUBGRADE SPECIAL	TON	858	858
* XX006444	MULCH, SPECIAL	ACRE	1.9	1.9
* XX146400	STORM SEWER REMOVAL	FOOT	201	201
* Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	105	105
* <del>XX006531</del>	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 7 1/2"	SQ YD	3121	3121
* <del>XX006532</del>	RESTRICTED DEPTH INLET TYPE B, TYPE 8 GRATE	EACH	2	2

\* SEE SPECIAL PROVISIONS  
Δ SPECIALTY ITEMS