

# SCHEDULE OF QUANTITIES

STORM SEWER REMOVAL ITEM NO. XX146400	
LOCATION	(FOOT)
410+28 - 410+35 LT	7
419+24 - 419+39 LT	15
423+58 RT	2
439+32 - 440+32 LT	100
440+32 - 440+79 LT	48
441+37 LT	5
441+80 LT	17
442+24 LT	6
443+62 LT	1
<b>TOTALS</b>	<b>201</b>

SUB-BASE GRANULAR MATERIAL, TYPE B ITEM NO. 31101000	
LOCATION	TON
408+57.9 - SCOVILL ST. (LT)	138
414+00 - McHENRY ST. (LT)	152
420+00 - MUMFORD DR. (LT)	392
430+66 - SILVER ST. (LT)	89
433+66 - HARDING DR. (LT)	252
442+00 - 444+36.6 LT	68
408+68 - MUMFORD DR. (RT)	586
430+66 - SILVER ST. (RT)	75
433+66 - 444+33 RT	328
SE CORNER COLORADO AVE.	20
AMBER LANE	93
<b>TOTALS</b>	<b>2193</b>

AGGREGATE SUBGRADE SPECIAL ITEM NO. XX006432	
LOCATION	TON
410+25 - 413+00 LT	205
411+20 - 413+66 RT	188
438+19 - 443+50 RT	465
<b>TOTALS</b>	<b>858</b>

PAVEMENT REMOVAL (SPECIAL) ITEM NO. 44004400	
LOCATION	(SQ. YD.)
410+07 LT - SCOVILL STREET	26.2
SCOVILL STREET - McHENRY STREET	78.6
McHENRY STREET - MUMFORD DRIVE	106.1
MUMFORD DRIVE - SILVER STREET	45.0
SILVER STREET - 440+29, 14.5' LT	52.2
441+31, 20.5' LT - HARDING DRIVE	9.6
HARDING DRIVE - 441+84, 25' LT	4.5
443+81, 24' LT - 444+37, 23.8' LT	0.7
410+01, 9.0' RT - 417+75, 9.5' RT	47.5
418+25, 9.5' RT - 424+73, 9.5 RT	38.8
424+73, 12.5' RT - MUMFORD DRIVE	18.6
MUMFORD DRIVE - 432+55.5, 26.4 RT	28.5
438+00, 14' RT - 438+19, 14' RT	3.2
438+19, 10.5 RT - 444+24, 22' RT	39.6
444+24, 22' RT - COLORADO AVENUE	7.9
<b>TOTALS</b>	<b>507</b>

DRIVEWAY PAVEMENT REMOVAL ITEM NO. 44000200	
LOCATION	(SQ. YD.)
410+02 LT	71.3
417+52 LT	37.3
419+72 RT	75.9
420+95 LT	18.2
423+24 RT	78.2
425+17 LT	26.0
425+92 LT	57.3
426+96 LT	49.5
428+51 LT	60.7
428+93 LT	37.9
429+27 LT	27.7
431+39 LT	38.8
431+62 LT	51.9
433+00 RT	109.7
435+38 LT	50.2
436+24 LT	51.4
436+79 RT	101.7
437+00 LT	61.2
437+62 LT	65.7
439+08 LT	70.8
439+60 LT	83.7
439+89 RT	73.4
441+30 RT	54.6
441+73 RT	167.4
443+29 LT	55.0
<b>TOTALS</b>	<b>1576</b>

COMBINATION CURB AND GUTTER REMOVAL ITEM NO. 44000500	
LOCATION	(FOOT)
408+59.7 - 409+72 LT	114.2
408+68 - 410+00.2 RT	132.2
SE CORNER PHILO & MUMFORD	31.4
430+42.8 - 436+37.5 RT	597.1
432+51 - 432+56 RT	5.0
440+29.4 - 441+30.5 LT	100.5
441+84 - 443+02.3 LT	118.0
443+56.5 - 444+36.6 LT	80.1
<b>TOTALS</b>	<b>1179</b>

REMOVE EXISTING CULVERTS ITEM NO. 50105210	
LOCATION	(FOOT)
413+08 - 413+76 LT	68
413+11 - 413+27 RT	16
422+56 - 422+71 LT	15
422+80 - 422+96 LT	16
423+42 - 423+60 LT	18
425+83 - 426+03 LT	20
439+68 - 440+08 RT	40
441+19 - 441+91 RT	72
<b>TOTALS</b>	<b>265</b>

CONCRETE HEADWALL REMOVAL ITEM NO. 50104400	
LOCATION	EACH
440+79 RT	1
441+91 RT	1
<b>TOTALS</b>	<b>2</b>

SIDEWALK REMOVAL ITEM NO. 44000600	
LOCATION	EACH
NW CORNER PHILO & SCOVILL	36.3
SW COR PHILO & SCOVILL	221.8
413+20 RT	126.5
SE CORNER PHILO & AMBER	516.8
NE CORNER PHILO & AMBER	427.7
SW CORNER PHILO & MCHENRY	116.3
NW CORNER PHILO & MCHENRY	156.0
420+47 - DRIVEWAY LT	171.5
DRIVEWAY - 421+09 LT	36.1
422+26 - 422+34 RT	80.2
423+07 - 423+41 RT	346.3
426+66 - 426+77 RT	79.6
428+28 - DRIVEWAY	31.7
428+86 - 429+00 LT	56.4
429+17 - 429+38 LT	85.5
SE CORNER PHILO & MUMFORD	20.4
SW CORNER PHILO & MUMFORD	264.7
NW CORNER PHILO & MUMFORD	230
NE CORNER PHILO & MUMFORD	20.8
431+33 - DRIVEWAY LT	4.0
DRIVEWAY - 431+45 LT	4.0
431+49 - DRIVEWAY LT	26.1
DRIVEWAY - 431+74 LT	19.5
431+60 - 431+66 RT	24.0
432+44 - DRIVEWAY RT	197.6
SW CORNER PHILO & SILVER 38' LT	168.9
SW CORNER PHILO & SILVER 57' LT	9.6
DRIVE - 433+53 RT	159.0
NE CORNER PHILO & SILVER	155.2
435+26 - DRIVEWAY LT	24.4
DRIVE - 435+48 LT	20.4
436+12 - DRIVEWAY LT	24.8
DRIVEWAY - 436+39 LT	39.2
436+48 - DRIVEWAY RT	115.5
DRIVEWAY - 437+06 RT	87.3
438+91 - DRIVEWAY LT	19.8
DRIVEWAY - 439+24 LT	16.1
439+43 - DRIVEWAY LT	19.6
DRIVEWAY - 439+79 LT	22.0
440+72 LT	49.8
SW CORNER PHILO & HARDING	47.6
441+37 - 441+61 RT	233.0
441+85 - 444+88 RT	2948.8
NW CORNER PHILO & HARDING	137.7
<b>TOTALS</b>	<b>7599</b>

PAVEMENT REMOVAL ITEM NO. 44000100	
LOCATION	(SQ. YD.)
433+38, 26.5' RT - 438+00, 14' RT	495.2
440+29, 19' LT - 441+31, 20.5' LT	68.2
AMBER LANE	282.1
<b>TOTALS</b>	<b>846</b>

SEEDING, CLASS 1 (SPECIAL) - 25000900 MULCH, SPECIAL - ITEM NO. XX006444	
LOCATION	ACRE
407+15 - 441+65 RT	0.95
441+90 RT - SE CORNER COLORADO	0.13
407+15 - 444+51 LT	0.79
<b>TOTALS</b>	<b>1.9 ACRE</b>


SODDING, SALT TOLERANT ITEM NO. 25200110	
LOCATION	(SQ. YD.)
427+63 - 429+50 RT	59
SE CORNER MUMFORD	8
NE CORNER MUMFORD - 432+50 RT	67
414+10 - 417+35 LT	73
417+60 - 418+45 LT	20
418+45 - 419+10 LT	17
421+15 - 421+65 LT	9
422+10 - 422+60 LT	9
422+90 - 423+40 LT	10
423+75 - 424+25 LT	9
424+60 - 425+10 LT	9
425+20 - 425+80 LT	11
426+05 - 426+90 LT	17
427+05 - 428+30 LT	22
<b>TOTALS</b>	<b>340</b>

NITROGEN FERTILIZER NUTRIENTS ITEM NO. 25000400	
LOCATION	POUND
407+15 - 441+65 RT	87
441+90 RT - SE CORNER COLORADO	12
407+15 - 444+51 LT	72
SOD LOCATIONS	6
<b>TOTALS</b>	<b>177</b>

PHOSPHORUS FERTILIZER NUTRIENT ITEM NO. 25000500	
LOCATION	POUND
407+15 - 441+65 RT	87
441+90 RT - SE CORNER COLORADO	12
407+15 - 444+51 LT	72
SOD LOCATIONS	6
<b>TOTALS</b>	<b>177</b>

POTASSIUM FERTILIZER NUTRIENT ITEM NO. 25000600	
LOCATION	POUND
407+15 - 441+65 RT	87
441+90 RT - SE CORNER COLORADO	12
407+15 - 444+51 LT	72
SOD LOCATIONS	6
<b>TOTALS</b>	<b>177</b>

SUPPLEMENTAL WATERING ITEM NO. 25200200	
LOCATION	UNIT
407+15 - 441+65 RT	73.6
441+90 RT - SE CORNER COLORADO	10.1
407+15 - 444+51 LT	61.2
<b>TOTALS</b>	<b>145</b>



CITY OF URBANA  
PUBLIC WORKS  
ENGINEERING DIVISION

DRAWN BY: PLS  
DESIGNED BY: CES  
CHECKED BY: GLJ  
CITY SECTION  
95-00305-01-PV

Philo Road Improvements  
Schedule of Quantities

SHEET NO.  
5  
OF  
62