

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET
TR 373	*	Vermilion	19	3
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

\*02-04130-00-BR

SEEDING, CLASS 2	
LOCATION	ACRE
STA. 8+00 TO STA. 9+76.86	0.17
STA. 10+23.14 TO STA. 12+00	0.14
<b>TOTAL</b>	<b>0.31</b>

MULCH, METHOD 2	
LOCATION	ACRE
STA. 8+00 TO STA. 9+76.86	0.17
STA. 10+23.14 TO STA. 12+00	0.14
<b>TOTAL</b>	<b>0.31</b>

PIPE CULVERTS, TYPE 1 ALUMINIZED CORRUGATED STEEL PIPE, 18" DIA	
LOCATION	FOOT
LT. STA 8+84 TO STA 9+16	32
<b>TOTAL</b>	<b>32</b>

PIPE CULVERT REMOVAL	
LOCATION	FOOT
LT. STA 9+60 TO STA 9+82	22
<b>TOTAL</b>	<b>22</b>

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
LT. STA 8+90 TO STA 9+10	17
<b>TOTAL</b>	<b>17</b>

CONSTRUCTION LAYOUT	
LOCATION	L SUM
SEC. 02-04130-00-BR	1
<b>TOTAL</b>	<b>1</b>

BITUMINOUS SURFACE TREATMENT, A-3 SPECIAL	
LOCATION	SQ YD
STA. 8+00 TO STA. 9+76.86	417
STA. 10+23.14 TO STA. 12+00	414
<b>TOTAL</b>	<b>831</b>

AGGREGATE BASE COURSE, TYPE A, 8"	
LOCATION	SQ YD
STA. 8+00 TO STA. 9+76.86	417
STA. 10+23.14 TO STA. 12+00	414
<b>TOTAL</b>	<b>831</b>

DSGN	K.J. Hoffmann					
DR	R.T. Mumm					
CHK	K.E. Brandau					
APVD	K.E. Brandau	NO.	DATE	REVISION	BY	APVD

**FRAUENHOFFER**

Frauenhoffer and Associates, P.C. Consulting Engineers  
3002 Crossing Court Champaign, IL 61822 217-351-6268

SCHEDULE OF QUANTITIES

CATLIN ROAD DISTRICT  
SECTION 02-04130-00-BR  
VERMILION COUNTY

SHEET	3
DWG NO.	5068-sch.dgn
DATE	FEB 2006
PROJ NO.	5068