

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-00027-01-PV	MASON	79	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MASON COUNTY			CITY OF HAVANA	
				1000	J000	SFTY-1A (1)	MFT (2)	LOCAL (3)
60609800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18	FOOT	664		576.3			87.7
67100100	MOBILIZATION	L SUM	1	0.30	0.30		0.20	0.20
• 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	0.30	0.30		0.20	0.20
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1038	1038				
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	9292	9292				
70301000	WORK-ZONE PAVEMENT MARKING REMOVAL	SQ FT	1552	1552				
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	14646	14646				
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	786		786			
Δ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	228		228			
• X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	784		784			
• X0322791	FILL EXISTING SANITARY SEWERS	CU YD	8				8	
• X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	5649		5649			
Δ • X0323449	REMOVE EXISTING WATER VALVE	EACH	3					3
Δ • X0323951	GATE VALVES, 4"	EACH	2					2
• X4066524	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	940	940				
• X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	38	38				
• X4420500	TEMPORARY PAVEMENT PATCH	SQ YD	934				763	171
Δ • X5640150	FIRE HYDRANT ASSEMBLY COMPLETE	EACH	5					5
• X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12		12			

NOTES: (1) MASON COUNTY PEDESTRIAN RAMPS ON EXISTING CURBS
 (2) CITY OF HAVANA STORM SEWER
 (3) CITY OF HAVANA WATER MAIN

•SEE SPECIAL PROVISION
 Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROMENADE STREET (C.H. 20)
 SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY RDJ
 HORIZ. CHECKED BY RXC
 DATE 11/10/18

02:39:11 PM
 02/02/2006 02:38 PM
 #FILES
 LAYOUT 9/6/05
 DRAWN RDJ 11/10/18
 REVIEWED RXC 2/3/06