

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-00027-01-PV	MASON	79	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ROADWAY REMOVAL AND DRAINAGE REMOVAL SCHEDULE

LOCATION						BITUMINOUS SURFACE REM - BUTT JOINT	PAVEMENT REMOVAL	COMB CONC CURB AND GUTTER REM	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	LOCATION						BITUMINOUS SURFACE REM - BUTT JOINT	PAVEMENT REMOVAL	COMB CONC CURB AND GUTTER REM	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS																				
						(SQ YD)	(SQ YD)	(FOOT)	(EACH)	(EACH)	(EACH)							(SQ YD)	(SQ YD)	(FOOT)	(EACH)	(EACH)	(EACH)																				
PROMENADE STREET																						ADAMS STREET																					
RT	STA	9+25.52	TO	RT	STA	9+40.31			22.0				STA	203+86.39	10.31'	RT							1																				
	STA	9+32.48		RT							1		SUBTOTAL												1																		
RT	STA	9+83.82	TO	RT	STA	9+95.01			22.0				PROMENADE STREET (DUE TO WATER MAIN)																														
	STA	9+92.60		RT							1		LT	STA	6+73.74	TO	LT	STA	6+83.88							19.0																	
	STA	9+94.00		RT	STA	10+00.00	25						LT	STA	12+86.63	TO	LT	STA	12+88.14							2.1																	
	STA	9+97.11		RT							1		LT	STA	16+81.69	TO	LT	STA	16+83.76							2.8																	
	STA	10+00.00		RT	STA	12+69.10		1116					LT	STA	17+27.90	TO	LT	STA	17+30.56							2.8																	
LT	STA	12+88.14	TO	LT	STA	12+91.32			22.0				LT	STA	20+67.90	TO	LT	STA	20+83.58							17.0																	
	STA	12+90.95		LT							1		LT	STA	21+45.85	TO	LT	STA	21+64.94							22.1																	
RT	STA	13+04.20	TO	RT	STA	13+08.69			12.0				STA	25+12.19	36.18'	LT								1																			
	STA	13+07.09		RT							1		LT	STA	28+91.92	TO	LT	STA	29+05.68							15.1																	
LT	STA	13+29.77	TO	LT	STA	13+31.63			5.0				STA	29+09.22	35.94'	LT								1																			
RT	STA	13+36.18	TO	RT	STA	13+60.47			34.0				STA	29+18.01	23.45'	LT								1																			
	STA	13+51.71		RT	STA	16+85.27		1282					LT	STA	36+99.06	TO	LT	STA	37+01.82							6.9																	
LT	STA	16+83.76	TO	LT	STA	16+86.32			22.0				SUBTOTAL												1	2																	
RT	STA	16+84.26	TO	RT	STA	16+86.93			22.0				INTERSECTIONS																														
	STA	16+85.92		RT							1		PROMENADE STREET / LAUREL STREET																														
	STA	16+95.73		RT							1		PROMENADE STREET / WASHINGTON STREET																														
LT	STA	17+30.56	TO	LT	STA	17+46.19			17.0				PROMENADE STREET / ADAMS STREET																														
RT	STA	17+31.91	TO	RT	STA	17+49.62			22.0				PROMENADE STREET / MARKET STREET																														
	STA	17+40.31		RT							1		PROMENADE STREET / JEFFERSON STREET																														
	STA	17+46.42		RT	STA	20+65.09		1311					PROMENADE STREET / FRANKLIN STREET																														
	STA	21+64.32		RT	STA	24+92.32		1358					PROMENADE STREET / MAIN STREET																														
	STA	23+15.35		RT							1		TOTAL						514	4182																							
RT	STA	24+79.99	TO	RT	STA	25+13.50			105.5				GRAND TOTAL																														
LT	STA	24+92.32	TO	LT	STA	25+13.13			35.5				601	13367	835	4	4	5																									
RT	STA	25+50.85	TO	RT	STA	25+94.99			56.0																																		
LT	STA	25+51.19	TO	LT	STA	25+66.27			28.0																																		
	STA	25+77.00		RT	STA	28+87.83		1288																																			
RT	STA	29+04.63	TO	RT	STA	29+07.65			5.0																																		
LT	STA	29+47.88	TO	LT	STA	29+68.21			33.0																																		
RT	STA	29+48.06	TO	RT	STA	29+63.95			28.0																																		
	STA	29+97.47		RT	STA	36+82.97		2830																																			
LT	STA	37+34.86	TO	LT	STA	37+48.65			22.0																																		
RT	STA	37+39.26	TO	RT	STA	37+61.35			34.0																																		
	STA	49+23.50		RT	STA	49+61.73		28																																			
	STA	56+35.00		RT	STA	56+45.00		34																																			
SUBTOTAL						87	9185	547	2	4	3																																

SIDEWALK REMOVAL SCHEDULE

LOCATION				SIDEWALK REMOVAL (SQ FT)	LOCATION				SIDEWALK REMOVAL (SQ FT)						
PROMENADE STREET (DUE TO WATER MAIN)					PROMENADE STREET (DUE TO ROADWAY)										
LT	STA	6+74.40	TO	LT	STA	7+47.04	290.6	LT	STA	12+80.17	TO	LT	STA	12+89.36	36.5
LT	STA	7+06.24	TO	LT	STA	7+10.10	11.2	LT	STA	13+31.83	TO	LT	STA	13+36.77	18.4
LT	STA	7+64.09	TO	LT	STA	8+04.52	161.7	LT	STA	16+78.64	TO	LT	STA	16+85.04	26.9
LT	STA	8+27.28	TO	LT	STA	8+62.63	141.4	LT	STA	17+33.63	TO	LT	STA	17+46.21	35.6
LT	STA	8+82.95	TO	LT	STA	9+36.43	249.9	LT	STA	24+99.64	TO	LT	STA	25+02.33	29.0
LT	STA	9+72.27	TO	LT	STA	10+48.80	306.1	RT	STA	25+59.26	TO	RT	STA	25+63.05	94.0
LT	STA	10+82.79	TO	LT	STA	11+14.18	125.6	LT	STA	25+60.14	TO	LT	STA	25+73.41	70.6
LT	STA	11+39.12	TO	LT	STA	12+80.17	602.8	LT	STA	29+54.46	TO	LT	STA	29+65.54	35.1
LT	STA	13+36.77	TO	LT	STA	15+26.56	820.6	RT	STA	29+55.70	TO	RT	STA	29+59.10	13.6
LT	STA	15+37.51	TO	LT	STA	15+65.80	113.2	LT	STA	31+52.28	TO	LT	STA	31+55.28	22.6
LT	STA	15+74.39	TO	LT	STA	16+78.64	482.4	SUBTOTAL				382.3			
LT	STA	17+29.88	TO	LT	STA	17+34.68	11.4	TOTAL				6001			
LT	STA	17+46.21	TO	LT	STA	18+78.02	515.5								
LT	STA	18+50.27	TO	LT	STA	18+56.28	10.3								
LT	STA	18+88.28	TO	LT	STA	19+48.83	242.2								
LT	STA	19+57.26	TO	LT	STA	19+84.14	107.5								
LT	STA	19+96.24	TO	LT	STA	20+79.39	332.6								
LT	STA	21+56.83	TO	LT	STA	22+36.22	317.6								
LT	STA	22+50.11	TO	LT	STA	23+12.20	248.4								
LT	STA	22+86.95	TO	LT	STA	22+88.94	6.9								
LT	STA	29+65.54	TO	LT	STA	30+51.67	319.1								
LT	STA	30+70.33	TO	LT	STA	31+25.71	221.5								
SUBTOTAL				5618.3											

NOT TO SCALE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PROMENADE STREET (C.H. 20)
SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY RDU
 HORIZ. CHECKED BY RXC
 DATE 11/7/05

18-11-16 AM
 82-12-2006, 10:11 AM
 8-FILE9
 LAYOUT 8/04/05
 DRAWN RQJ 11/7/05
 REVIEWED RJC 11/18/05