

**CONTRACT NO. 97270**

## SUMMARY OF QUANTITIES


FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK		
TEMPLATE		
AREAS		
CHECKED.		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK		
TEMPLATE		
AREAS		
CHECKED.		
NO.		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	589
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2432
20400800	FURNISHED EXCAVATION	CU YD	1045
20800150	TRENCH BACKFILL	CU YD	20
25000100	SEEDING, CLASS 1	ACRE	1.5
25100630	EROSION CONTROL BLANKET	SQ YD	157
28000300	TEMPORARY DITCH CHECK	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	1103
28000500	INLET AND PIPE PROTECTION	EACH	3
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	6
28200200	FILTER FABRIC	SQ YD	6
30200850	PROCESSING MODIFIED SOILS 16"	SQ YD	6615
30201500	LIME	TON	219
35100100	AGGREGATE BASE COURSE, TYPE A	TON	625
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	6804
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2516
42000201	PORTLAND CEMENT CONCRETE PAVEMENT, 7" (JOINTED)	SQ YD	1515
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	1224
48100100	AGGREGATE SHOULDER TYPE A	TON	88
542A0213	PIPE CULVERTS, CLASS A, TYPE 1 8"	FOOT	22
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 18"	FOOT	24

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60615400	PAVED DITCH TYPE A-15	FOOT	106
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	97
73000100	WOOD SIGN SUPPORT	FOOT	360
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	9168
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	83
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	208
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	849
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	849
XX002208	6" DIAMETER PIPE BOLLARD, CONCRETE FILLED	EACH	7
XX003816	FURNISHING AND INSTALLING CONCRETE WHEEL STOPS	EACH	25
X0322330	Handicap SIGN	EACH	8
* XX006458	PASSENGER SHELTER	L SUM	1
XX006456	PASSENGER SHELTER REMOVAL	L SUM	1
* XX005505	OUTDOOR LIGHT IMPROVEMENTS	L SUM	1
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2
* XX006455	WATER SERVICE AND GROUND HYDRANT	L SUM	1
XX006457	WHEEL STOP REMOVAL AND REPLACEMENT	EACH	100

\* SPECIALTY ITEMS

 <b>Juneau Associates, Inc. P.C.</b> CONSULTING ENGINEERS AND LAND SURVEYORS 200 State Street, P.O. Box 1325 Duquoin, Illinois 62048-4725 Phone: (618)877-1400 / (618)462-5525 Fax: (618)462-5511		<b>SUMMARY OF QUANTITIES</b> HIGHLAND PARK-RIDE IMPROVEMENTS MADISON COUNTY TRANSIT HIGHLAND, ILLINOIS SECTION No. 00-00012-00-PK	
REVISIONS NO. DATE BY REMARKS		SCALE:	
DSN. BY: RGL/AJW DATE: 12/20/05 DWN. BY: RGL/AJW DATE: 12/20/05 CHK'D: RAK DATE: 12/20/05		SHEET 3 OF 18 SHTS	
DWG. NO.		JOB NO. E054401 DWG NAME:	