

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	130 RS-2	WILLIAMSON	58	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE	UNIT	1000-1A
				URBAN ROADWAY HES SAFETY FED STATE 90% 10%
X0300351	CONCRETE STEP REMOVAL		EACH	3
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105		TONS	1,700
X7015000	CHANGEABLE MESSAGE SIGN		CAL MO	1
20200100	EARTH EXCAVATION		CU YD	420
20800150	TRENCH BACKFILL		CU YD	115
25100630	EROSION CONTROL BLANKET		SQ YD	471
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"		SQ YD	1288
35500600	BITUMINOUS BASE COURSE 9"		SQ YD	404
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	1,899
40800040	INCIDENTAL BITUMINOUS SURFACING		TON	74
40600300	AGGREGATE (PRIME COAT)		TON	32
40600990	TEMPORARY RAMP		SQ YD	72
42000200	PORTLAND CEMENT CONCRETE PAVEMENT, 7"		SQ YD	562
42001200	PAVEMENT FABRIC		SQ YD	562
42001300	PROTECTIVE COAT		SQ YD	803
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH		SQ YD	80
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	210
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"		SQ YD	20,603
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)		SQ YD	88
44000100	PAVEMENT REMOVAL		SQ YD	404
44000200	DRIVEWAY PAVEMENT REMOVAL		SQ YD	80
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	684
44000600	SIDEWALK REMOVAL		SQ FT	562
44201811	CLASS D PATCHES, TYPE I, 14 INCH		SQ YD	69
44201815	CLASS D PATCHES, TYPE II, 14 INCH		SQ YD	217
44201819	CLASS D PATCHES, TYPE III, 14 INCH		SQ YD	33
44201821	CLASS D PATCHES, TYPE IV, 14 INCH		SQ YD	90
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT		FOOT	15,650
50300225	CONCRETE STRUCTURES		CU YD	4
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	250
54248510	CONCRETE COLLAR		CU YD	0.32
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"		FOOT	362
60243500	INLETS, SPECIAL, TYPE 3, 6'		EACH	4
60300305	FRAMES AND LIDS TO BE ADJUSTED		EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12		FOOT	738
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	3
67100100	MOBILIZATION		L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21		L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501		L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606		L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801		L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DAY	6
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	2,504
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	556
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	9,294
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	186
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	4,862
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	556
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		FOOT	9,294
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"		FOOT	186

PLOT DATE = 2/16/2006
 FILE NAME = c:\p3\p3\va\021005\03010651.m32
 PLOT SCALE = 50.00000 / IN.
 USER NAME = carlsonej