

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	104 RS-4	UNION	24	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE	1000-1A
		UNIT	URBAN ROADWAY HES 90% FED 10% STATE
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	190
X4066920	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N105	TON	92
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQYD	2122
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1
20200100	EARTH EXCAVATION	CUYD	91
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQYD	72
25100630	EROSION CONTROL BLANKET	SQYD	102
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQYD	416
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQYD	132
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	203
40600300	AGGREGATE (PRIME COAT)	TON	4
40600990	TEMPORARY RAMP	SQYD	42
42001300	PROTECTIVE COAT	SQYD	158
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	72
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SOFT	90
44000100	PAVEMENT REMOVAL	SQYD	184
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	130
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	72
44000600	SIDEWALK REMOVAL	SOFT	40
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQYD	85
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQYD	5
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1255
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	298
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	LSUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	167
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SOFT	18
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1535
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	68
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	184
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SOFT	803
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SOFT	18
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	68
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	184
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1535
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15

* SPECIALTY ITEMS

PLOT DATE = 2/6/2006
 FILE NAME = c:\prow\msta\9022105\9022105.dgn
 PLOT SCALE = 50.001 / IN.
 USER NAME = russellr