

# SUMMARY OF QUANTITIES

COUNTY:	Pope
ROUTE:	FAP 132 IL 145
FUNDING:	80%FED 20%STATE ✓
LOCATION:	RURAL ✓
TOTAL QUANTITY	ROADWAY 0005 ✓

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY
25000200	SEEDING, CLASS 2	ACRE	1.6	1.6
25000350	SEEDING, CLASS 7	ACRE	1.6	1.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	100	100
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100	100
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	100	100
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2	2
25100105	MULCH, METHOD 1	ACRE	1.6	1.6
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	160	160
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	31467	31467
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	1924	1924
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	258	258
40600990	TEMPORARY RAMP	SQ YD	64	64
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	4184	4184
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	55	55



REV. 4-12-17

# SUMMARY OF QUANTITIES - CONT

COUNTY:	Pope
ROUTE:	FAP 132 IL 145
FUNDING:	80%FED 20%STATE
LOCATION:	RURAL
TOTAL QUANTITY	ROADWAY 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	45901	45901
44201361	CLASS C PATCHES, TYPE I, 11 INCH	SQ YD	254	254
44201365	CLASS C PATCHES, TYPE II, 11 INCH	SQ YD	133	133
44201369	CLASS C PATCHES, TYPE III, 11 INCH	SQ YD	18	18
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1019	1019
48203100	HOT-MIX ASPHALT SHOULDERS	TON	79	79
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	LSUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	LSUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5217	5217
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1739	1739
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	51828	51828
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	51828	51828



\* SPECIALTY ITEM

REV. 4-12-17

19 \*

# SUMMARY OF QUANTITIES - CONT

COUNTY:	Pope
ROUTE:	FAP 132 IL 145
FUNDING:	80%FED 20%STATE
LOCATION:	RURAL
TOTAL QUANTITY	ROADWAY 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0005
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	217	217
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	217	217
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	153	153
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	17276	17276
Z0034105	MATERIAL TRANSFER DEVICE	TON	4184	4184

6

\* SPECIALTY ITEM

△ REV. 4-12-17

# IL 145 MAINLINE RESURFACING SCHEDULE

LOCATION STATION TO STATION	LENGTH	ROADWAY WIDTH	HOT-MIX ASP. SURF. REMOV. - BUTT JT.	TEMP RAMP	HMA SUR. REMOVAL 1/2" **	HOT-MIX ASP. SUR. CSE., MIX C, N 70 (1 1/2") **	LEVELING BINDER (MM) N70 (3/4") **	BIT. MAT. (TACK COAT) *	HOT-MIX ASPHALT SHOULDLERS	NOTES			
											FOR INFORMATIONAL PURPOSE ONLY		
											(FT)	(FT)	(SQ YD)
<b>MAINLINE: STA.112+75 TO STA. 285+95</b>													
	112+75.00	TO	119+47.00			49	12						
LT	112+75.00	TO	119+47.00	672	11			821	70	35	554		
RT	112+75.00	TO	119+47.00	672	11			821	70	35	554		
	119+47.00	TO	140+00.00										
LT	119+47.00	TO	140+00.00	2053	11			2509	213	106	1,694		
RT	119+47.00	TO	140+00.00	2053	11			2509	213	106	1,694		
	140+00.00	TO	150+06.00	1006	11			1230	105	52	830		
RT	140+00.00	TO	150+06.00	1006	11			1230	105	52	830		
<b>STA. EQ. STA. 150+06 BK=STA.149+36 AH</b>													
LT	149+36.00	TO	154+82.00	546	11			667	57	29	450		
RT	149+36.00	TO	154+82.00	546	11			667	57	29	450		
	154+82.00		155+17.00										
LT	154+82.00	TO	155+17.00	35	12			47	3	0	32	14	HMA SHOULDERS STA.154+21 TO STA. 157+26
RT	154+82.00	TO	155+17.00	35	12			47	3	0	32	14	HMA SHOULDERS STA.152+78 TO STA. 155+70
	155+17.00	TO	170+11.00										
LT	155+17.00	TO	170+11.00	1494	11			1,869	155	77	1,233	25	HMA SHOULDERS STA.169+30 TO STA. 173+70
RT	155+17.00	TO	170+11.00	1494	11	80	20	1882	155	77	1,233	26	HMA SHOULDERS STA.168+00 TO STA. 172+65
<b>OMISSION: STRUCTURAL NUMBER 076-0015</b>											<b>STA. 170+11 TO STA. 171+88</b>		
	171+88.00	TO	211+00.00			80	20						<b>BOX CULVERT (SN 076-2003) STA. 211+00</b>
LT	171+88.00	TO	211+00.00	3912	11			4802	406	201	3,227		
RT	171+88.00	TO	211+00.00	3912	11			4790	406	201	3,227		
	211+00.00	TO	250+00.00										
LT	211+00.00	TO	250+00.00	3900	11			4767	405	201	3,218		
RT	211+00.00	TO	250+00.00	3900	11			4767	405	201	3,218		
	250+00.00	TO	285+95.00	3595	11			4394	373	185	2,966		
RT	250+00.00	TO	285+95.00	3595	11	49	12	4394	373	185	2,966		
<b>MAINLINE TOTALS</b>						<b>258</b>	<b>64</b>	<b>42,212</b>	<b>3,574</b>	<b>1,772</b>	<b>28,407</b>	<b>79</b>	

\*NOTE: SEE GUTTER SCHEDULE, SIDE ROAD, AND ENTRANCE SCHEDULES FOR ADDITIONAL QUANTITIES

\*\*NOTE: SEE GUTTER SCHEDULE FOR ADDITIONAL QUANTITIES

▲ REVISED SHEET 4-12-2017

FILE NAME : p:\IL145\BID\BID\REG\Illinois.gov\PWIDOT\Do	USER NAME : jackson	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 145 MAINLINE RESURFACING SCHEDULE</b>	F.A.P. RTE. 132	SECTION 12RS-4	COUNTY POPE	TOTAL SHEETS 26	SHEET NO. 11
PLT SCALE : 100.0000 / in.	PLT DATE : 4/10/2017	CHECKED -	REVISED -	SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT CONTRACT NO. 78558				

# GUTTER SCHEDULE

LOCATION STATION TO STATION				GUTTER LENGTH	ROADWAY WIDTH	HMA SURFACE REMOVAL 1/2" **	LEVELING BINDER (MM) N70 (3/4") **	BIT MAT. (TACK COAT) *	GRADING AND SHAPING	HOT-MIX ASP. SUR. CSE., MIX C, N 70 (1 1/2") **
				FOR INFORMATIONAL PURPOSE ONLY		(FT)	(FT)	(SQ YD)	(TON)	(LBS)
<b>MAINLINE: STA.112+75 TO STA. 285+95</b>										
LT	112+75.00	TO	149+70.00	3695	2	280	35	555	37	147
RT	112+94.00	TO	119+47.00	653	2	821	7	98	7	26
LT	149+85.00	TO	154+76.00	491	2	109	5	74	5	20
RT	+00	TO	+00	0	2	0	0	0	0	0
LT	167+85.00	TO	169+30.00	145	2	32	2	22	1	6
RT	+00	TO	+00	0	2	0	0	0	0	0
LT	179+76.00	TO	183+80.00	404	2	90	4	61	4	16
RT	172+65.00	TO	201+00.00	2835	2	630	27	426	28	113
LT	204+60.00	TO	208+00.00	340	2	76	4	51	3	14
RT	203+50.00	TO	208+00.00	450	2	100	5	68	5	18
LT	+00	TO	+00	0	2	0	0	0	0	0
RT	228+80.00	TO	230+00.00	120	2	27	2	18	1	5
LT	241+76.00	TO	251+25.00	949	2	211	9	143	9	38
RT	230+00.00	TO	251+14.00	2114	2	470	20	318	21	84
LT	+00	TO	+00	0	2	0	0	0	0	0
RT	252+02.00	TO	260+00.00	798	2	177	8	120	8	32
LT	+00	TO	+00	0	2	0	0	0	0	0
RT	260+00.00	TO	274+40.00	1440	2	320	14	216	14	57
LT	281+40.00	TO	285+95.00	455	2	101	5	69	5	18
RT	281+40.00	TO	285+95.00	455	2	101	5	69	5	18
<b>SUBTOTAL</b>						<b>3,690</b>	<b>152</b>	<b>2,308</b>	<b>153</b>	<b>609</b>

\* NOTE: MAINLINE RESURFACING, SIDE ROAD, AND ENTRANCE SCHEDULES FOR ADDITIONAL QUANTITIES.

\*\* NOTE: SEE MAINLINE RESURFACING SCHEDULE FOR ADDITIONAL QUANTITIES.

▲ REVISED SHEET 4-12-2017

FILE NAME :	USER NAME : jacksonc	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CURB AND GUTTER SCHEDULE</b>	F.A.P. RTE. 132	SECTION 12RS-4	COUNTY POPE	TOTAL SHEETS 26	SHEET NO. 13
Default	Documents\DOT Offices\District 9\Projects\785\DRAWING\CAD\Sheets\78558 Sheet	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT SCALE = 100.0000' / in.	DATE -	REVISED -							
	PLOT DATE = 4/10/2017									ILLINOIS FED. AID PROJECT