

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2005-12
Various Counties
Sheet 2 of 82
Contract Number 44872

Summary of Quantities

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	URBAN	RURAL
T9990710	REMOVE & REINSTALL WALKWAY	FOOT	554.80		554.80
T9992300	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	736.43	466.10	270.33
T9992530	REPLACE / TIGHTEN CLIPS PER SIGN	EACH	4.00		4.00
T9992600	RE-ERECT SIGN PANEL	SQ FT	69.00		69.00
T9992700	REMOVE & REINSTALL SIGN PANEL	SQ FT	4,192.00		4,192.00
T9995400	FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	32.00	16.00	16.00
T9996200	REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	14.00	14.00	
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	25.00	25.00	
T9997255	FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	8.00	4.00	4.00
T9997700	FURNISH & INSTALL SAFETY CHAIN	EACH	56.00	16.00	40.00
T9998600	TIGHTEN CANTILEVER CONNECTION	EACH	2.00	2.00	
T9998815	REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	89.00		89.00
T9998860	DRILL WEEP HOLE	EACH	10.00	10.00	
T9998897	REPLACE HANDRAIL SUPPORT	EACH	3.00		3.00
T9998910	FURNISH & INSTALL METAL SCREEN	EACH	8.00		8.00
T9998995	DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	2.00		2.00
X0324397	RELOCATE ELECTRIC SERVICE	EACH	17.00		17.00
X7330095	OVERHEAD SIGN STRUCTURE - CANTLEVER, MONOTUBE	FOOT	20.00		20.00
67100100	MOBILIZATION	L SUM	1.00	0.13	0.87