

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

Various Routes
OVD SIN STR REP & REPL 2005-12
Various Counties
Sheet 4 of 82
Contract Number 44872

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 1	DISTRICT 2	DISTRICT 3	DISTRICT 4	DISTRICT 5	DISTRICT 6
REMOVE & REINSTALL WALKWAY	FOOT	554.80		65.00	36.00	78.00	217.50	158.30
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	736.43	466.10	53.50	216.83			
REPLACE / TIGHTEN CLIP PER SIGN	EACH	4.00				1.00		3.00
REINSTALL SIGN PANEL	SQ FT	69.00		69.00				
REMOVE & REINSTALL SIGN PANEL	SQ FT	4,192.00		293.50	313.75	610.00	1,464.75	1,510.00
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	32.00	16.00	4.00	12.00			
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	14.00	14.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	25.00	25.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	8.00	4.00	1.00	3.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	56.00	16.00	8.00	8.00	8.00	8.00	8.00
TIGHTEN CANTILEVER CONNECTION	EACH	2.00	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	89.00		21.00		16.00	28.00	24.00
DRILL WEEP HOLE	EACH	10.00	10.00					
REPLACE HANDRAIL SUPPORT	EACH	3.00		3.00				
FURNISH & INSTALL METAL SCREEN	EACH	8.00						8.00
RELOCATE ELECTRIC SERVICE	EACH	17.00		5.00	4.00	3.00	4.00	1.00
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	2.00						2.00