

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2005-12
Various Counties
Sheet 6 of 82
Contract Number 44872

District 1
Schedule of Locations for Truss Repair & Replacement

Location No.:	1-01	State I.D. No.:	1S016I290R000.5 (S-18)P4			
County:	Cook	Route:	I-290	0.5	Direction:	EB
Description of Work	Unit	Quantity				
Remove & Re-erect Overhead Sign Structure - Span	Each	1.00				
Structural Steel Support Overhead Sign Structure	Each	2.00				
Furnish & Install Internal Truss Damper	Each	1.00				
Furnish & Install Safety Chain	Each	4.00				
Overhead Sign Support Grout Repair	Each	4.00				
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00				
Furnish & Install Saddle Shim Block	Each	4.00				
Overhead Sign Structure Walkway	Foot	110.75				
This work shall be completed during District 1 night-time hours.						

Location No.:	1-02	State I.D. No.:	1S016I290R000.00 (S-19)P2				
County:	Cook	Route:	I-290	M.P.:	0	Direction:	EB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure - Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	4.00					
Overhead Sign Support Grout Repair	Each	4.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
Furnish & Install Saddle Shim Block	Each	4.00					
Overhead Sign Structure Walkway	Foot	112.75					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-03	State I.D. No.:	1S016S053L000.00-010 (S-20)R1				
County:	Cook	Route:	IL 53	M.P.:	0	Direction:	SB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Overhead Sign Structure Grout Repair	Each	4.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
Furnish & Install Saddle Shim Block	Each	4.00					
Overhead Sign Structure Walkway	Foot	141.25					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-04	State I.D. No.:	1S016S053L000.2 (S-17)P3				
County:	Cook	Route:	IL 53	M.P.:	0.2	Direction:	SB
Description of Work	Unit	Quantity					
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00					
Structural Steel Sign Support Overhead Sign Structure	Each	2.00					
Furnish & Install Internal Truss Damper	Each	1.00					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Grout Repair	Each	4.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
Furnish & Install Saddle Shim Block	Each	4.00					
Overhead Sign Structure Walkway	Foot	101.33					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-05	State I.D. No.:	1C016I290R001.0-000 (C-4)O2				
County:	Cook	Route:	I-290	M.P.:	1.0	Direction:	EB
Description of Work	Unit	Quantity					
Furnish & Install Safety Chain	Each	2.00					
Tighten Cantilever Connection	Each	2.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	1.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-06	State I.D. No.:	1S016I355L030.2 (TR-125)T4				
County:	Cook	Route:	I-355	M.P.:	30.2	Direction:	SB
Description of Work	Unit	Quantity					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-07	State I.D. No.:	1C022I290L006.3 (C-1)J1				
County:	Du Page	Route:	I-290	M.P.:	66.3	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Support Grout Repair	Each	1.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	1.00					
Drill Weep Hole	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-08	State I.D. No.:	1C022I290L005.6 (C-2)J5				
County:	Du Page	Route:	I-290	M.P.:	5.6	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Support Grout Repair	Each	1.00					
Drill Weep Hole	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-09	State I.D. No.:	1C022I290L005.4 (C-3)K1				
County:	Du Page	Route:	I-290	M.P.:	5.4	Direction:	WB
Description of Work	Unit	Quantity					
Overhead Sign Structure Grout Repair	Each	1.00					
Drill Weep Hole	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-10	State I.D. No.:	1S016S053L000.0-007 (TS-1)Y1				
County:	Cook	Route:	IL 53	M.P.:	0.0	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Grout Repair	Each	2.00					
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-11	State I.D. No.:	1S022I290R010.4 (TE-3)B2				
County:	Du Page	Route:	I-290	M.P.:	10.4	Direction:	EB
Description of Work	Unit	Quantity					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Grout Repair	Each	2.00					
Drill Weep Hole	Each	4.00					
This work shall be completed during District 1 night-time hours.							

Location No.:	1-12	State I.D. No.:	1S022I290L010.9 (TW-8)A1				
County:	Du Page	Route:	I-290	M.P.:	10.9	Direction:	WB
Description of Work	Unit	Quantity					
Furnish & Install Safety Chain	Each	2.00					
Overhead Sign Structure Grout Repair	Each	2.00					
This work shall be completed during District 1 night-time hours.							