

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
OVD SIN STR REP & REPL 2005-12  
Various Counties  
Sheet 14 of 82  
Contract Number 44872

District 2  
Schedule of Locations for Truss Repair & Replacement

Location No.:	2-01	State I.D. No.:	2C081S092L029.5(139)				
County:	Rock Island	Route:	IL 92	M.P.:	0.5	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	69.75					
REMOVE & REINSTALL WALKWAY	FOOT	16.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE CANTILEVER TYPE I-C-A	FOOT	25.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	4.80					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This sign structure is being completely replaced and downsized.							

Location No.:	2-03	State I.D. No.:	2C081S092L029.4(140)				
County:	Rock Island	Route:	il 92	M.P.:	29.4	Direction:	sb
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	78.00					
REMOVE & REINSTALL WALKWAY	FOOT	16.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE CANTILEVER TYPE I-C-A	FOOT	25.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	4.80					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This sign structure is being completely replaced and downsized.							

Location No.:	2-05	State I.D. No.:	2S101S020R009.5 (1)				
County:	Winnebago	Route:	US 20	M.P.:	9.5	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	53.50					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.60					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	5.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					

Location No.:	2-02	State I.D. No.:	2C081S092L028.8(144)				
County:	Rock Island	Route:	IL 92	M.P.:	28.8	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	71.50					
REMOVE & REINSTALL WALKWAY	FOOT	16.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE CANTILEVER TYPE I-C-A	FOOT	25.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	4.80					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This sign structure is being completely replaced and downsized.							

Location No.:	2-04	State I.D. No.:	2C081S092R028.6 (146)				
County:	Rock Island	Route:	IL 92	M.P.:	28.6	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	74.25					
REMOVE & REINSTALL WALKWAY	FOOT	17.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE I-C-A	FOOT	25.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	4.80					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
REPLACE HANDRAIL SUPPORT	EACH	3.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This sign structure is being completely replaced and downsized.							

Location No.:	2-06	State I.D. No.:	2M098S078R018.05				
County:	Whiteside	Route:	IL 78	M.P.:	18.05	Direction:	NB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE - CANTILEVER, MONOTUBE	FOOT	20.00					
RE-ERECT SIGN PANEL	SQ FT	69.00					
This sign structure shall be designed to fit on an existing concrete foundation with 1 1/2 inch diameter anchor bolts with a 6 bolt 16 inch diameter bolt pattern.							