

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2005-12
Various Counties
Sheet 34 of 82
Contract Number 44872

District 3
Schedule of Locations for Truss Repair & Replacement

Location No.:	3-01		State I.D. No.:	3S057I055L000.9				
County:	McLean	Route:	I-55	M.P.:	0.9	Direction:	SB	
Description of Work							Unit	Quantity
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN							EACH	1.00
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE							EACH	2.00
FURNISH & INSTALL SADDLE SHIM BLOCK							EACH	4.00
FURNISH & INSTALL INTERNAL TRUSS DAMPER							EACH	1.00
FURNISH & INSTALL SAFETY CHAIN							EACH	2.00
OVERHEAD SIGN STRUCTURE WALKWAY							FOOT	72.00
REMOVE CONCRETE FOUNDATION-OVERHEAD							EACH	2.00
DRILLED SHAFT CONCRETE FOUNDATION							CU YD	21.60
RELOCATE ELECTRIC SERVICE							EACH	1.00

Location No.:	3-04		State I.D. No.:	3S057I074R133.9				
County:	McLean	Route:	I-74	M.P.:	133.9	Direction:	EB	
Description of Work							Unit	Quantity
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN							EACH	1.00
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE							EACH	2.00
FURNISH & INSTALL SADDLE SHIM BLOCK							EACH	4.00
FURNISH & INSTALL INTERNAL TRUSS DAMPER							EACH	1.00
FURNISH & INSTALL SAFETY CHAIN							EACH	2.00
OVERHEAD SIGN STRUCTURE WALKWAY							FOOT	68.50
REMOVE CONCRETE FOUNDATION - OVERHEAD							EACH	2.00
DRILLED SHAFT CONCRETE FOUNDATIONS							CU YD	21.60
RELOCATE ELECTRIC SERVICE							EACH	1.00

Location No.:	3-02		State I.D. No.:	3S057I074L134.8				
County:	McLean	Route:	I-74	M.P.:	134.8	Direction:	WB	
Description of Work							Unit	Quantity
REMOVE OVERHEAD SIGN STRUCTURE-SPAN							EACH	1.00
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE							EACH	2.00
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A							FOOT	50.00
REMOVE & REINSTALL WALKWAY							FOOT	36.00
REMOVE & REINSTALL SIGN PANEL							SQ FT	313.75
FURNISH & INSTALL SAFETY CHAIN							EACH	2.00
REMOVE CONCRETE FOUNDATION-OVERHEAD							EACH	2.00
DRILLED SHAFT CONCRETE FOUNDATION							CU YD	12.00
RELOCATE ELECTRIC SERVICE							EACH	1.00
This sign structure is being completely replaced.								

Location No.:	3-03		State I.D. No.:	3S057I074L135.7				
County:	McLean	Route:	I-74	M.P.:	135.7	Direction:	WB	
Description of Work							Unit	Quantity
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN							EACH	1.00
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE							EACH	2.00
FURNISH & INSTALL SADDLE SHIM BLOCK							EACH	4.00
FURNISH & INSTALL INTERNAL TRUSS DAMPER							EACH	1.00
FURNISH & INSTALL SAFETY CHAIN							EACH	2.00
OVERHEAD SIGN STRUCTURE WALKWAY							FOOT	76.33
REMOVE CONCRETE FOUNDATION-OVERHEAD							EACH	2.00
DRILLED SHAFT CONCRETE FOUNDATION							CU YD	21.60
RELOCATE ELECTRIC SERVICE							EACH	1.00