

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2005-12
Various Counties
Sheet 49 of 82
Contract Number 44872

District 4
Schedule of Locations for Truss Repair & Replacement

Location No.:	4-01	State I.D. No.:	4C090U024R001.0				
County:	Tazewell	Route:	US 24	M.P.:	1	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE CANTILEVER 2CA3-0X5-6	FOOT	29.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	6.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	140.00					
REMOVE & REINSTALL WALKWAY	FOOT	20.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					

Location No.:	4-02	State I.D. No.:	4C072S006R009.2				
County:	Peoria	Route:	IL 6	M.P.:	9.2	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE CANTILEVER 2CA3-0X5-6	FOOT	28.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	6.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	159.50					
REMOVE & REINSTALL WALKWAY	FOOT	16.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					

Location No.:	4-03	State I.D. No.:	4C090U024L000.9				
County:	Tazewell	Route:	US 24	M.P.:	0.9	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE CANTILEVER 2CA3-0X5-6	FOOT	30.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	8.70					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	232.50					
REMOVE & REINSTALL WALKWAY	FOOT	22.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	1.00					

Location No.:	4-04	State I.D. No.:	4C102I074L114.8				
County:	Woodford	Route:	I-74	M.P.:	114.8	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER,TYPE II-C-A (36" X 5'-6")	FOOT	30.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.70					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	78.00					
REMOVE & REINSTALL WALKWAY	FOOT	20.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
There is no sign lighting on this structure.							