

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

*Various Routes  
OVD SIN STR REP & REPL 2005-12  
Various Counties  
Sheet 59 of 82  
Contract Number 44872*

*District 5  
Schedule of Locations for Truss Repair & Replacement*

Location No.:	5-01	State I.D. No.:	5S010I074R179.0				
County:	Champaign	Route:	I-74	M.P.:	179	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE 1A	FOOT	75.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	258.25					
REMOVE & REINSTALL WALKWAY	FOOT	60.50					

Location No.:	5-02	State I.D. No.:	5S010I074L179.22				
County:	Champaign	Route:	I-74	M.P.:	179.22	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE 1A	FOOT	75.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	393.75					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL WALKWAY	FOOT	60.50					

Location No.:	5-03	State I.D. No.:	5S010I072R180.76				
County:	Champaign	Route:	I-72	M.P.:	180.76	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE SPAN TYPE 1A	FOOT	88.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	368.75					
REMOVE & REINSTALL WALKWAY	FOOT	30.50					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					

Location No.:	5-04	State I.D. No.:	5S010U045L012.30				
County:	Champaign	Route:	US 45	M.P.:	12.3	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE SPAN, TYPE I-A	FOOT	84.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	444.00					
REMOVE & REINSTALL WALKWAY	FOOT	66.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	10.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					