

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
OVD SIN STR REP & REPL 2005-12  
Various Counties  
Sheet 70 of 82  
Contract Number 44872

District 6  
Schedule of Locations for Truss Repair & Replacement

Location No.:	6-01	State I.D. No.:	6S0751072R002.7				
County:	Pike	Route:	I-72	M.P.:	2.7	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE III-A	FOOT	119.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	429.00					
REMOVE & REINSTALL WALKWAY	FOOT	46.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	8.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
FURNISH & INSTALL METAL SCREEN	EACH	4.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
This structure is being downsized from a Type IV truss to a Type III truss.							

Location No.:	6-04	State I.D. No.:	6S0541055L126.5				
County:	Logan	Route:	I-55	M.P.:	126.5	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A	FOOT	100.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	241.00					
REMOVE & REINSTALL WALKWAY	FOOT	32.30					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	10.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00					

Location No.:	6-02	State I.D. No.:	6S0751072L005.3				
County:	Pike	Route:	I-72	M.P.:	5.3	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A	FOOT	91.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	406.00					
REMOVE & REINSTALL WALKWAY	FOOT	46.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
FURNISH & INSTALL METAL SCREEN	EACH	4.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
This structure is being downsized from a Type IV truss to a Type III truss.							

Location No.:	6-03	State I.D. No.:	6S0541055L128.2				
County:	Logan	Route:	I-55	M.P.:	128.2	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A	FOOT	107.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	434.00					
REMOVE & REINSTALL WALKWAY	FOOT	34.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	2.00					
This structure is being downsized from a Type IV truss to a Type II truss. There is no sign lighting on this structure.							