

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
*C2012772	SHRUB, VIBURNUM PRUNIFOLIUM, (BLACKHAW VIBURNUM), 6' HEIGHT, BALLED AND BURLAPPED	EACH	12	12			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
*X0323000	8-CIRCUIT 240/120 PANEL	EACH	1				1
*X0323001	METER SOCKET PER COM-ED	EACH	1				1
*X0323002	TEMPORARY ELECTRICAL SERVICE CONNECTION	EACH	1				1
*X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO 6 1C (GREEN)	FOOT	380				380
X0712400	TEMPORARY PAVEMENT	SQ YD	4855	4855			
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	315	315			
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	369	369			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3			
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	78	78			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	256	256			
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	259	259			
*X8410112	REMOVE TEMPORARY LIGHTING UNITS	L SUM	1				1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z002800	FENCE REMOVAL	FOOT	214	214			
Z0024400	FILTER FABRIC	SQ YD	74			74	
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	8	8			
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	6	6			

Δ SFTY-3N

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
XX004900	TURF REINFORCEMENT MAT	SQ YD	75	75			
XX001452	CONCRETE MASONRY BULKHEAD	EACH	1			1	
*X8210405	LUMINAIRE SHIELD	EACH	1				1
Z0076600	TRAINEES	Hour	1,000	1,000			

© 4080

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14 OVER LAWRENCE CREEK
SUMMARY OF QUANTITIES

DATE: 2-15-05

DRAWN BY CLG
CHECKED BY JJD



#62391

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
066	21 (B&G) R	McHENRY	66	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

3287SHT3.DGN