

#62391

STAGE I

EARTHWORK SCHEDULE							
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED FOR FURNISH EMBANKMENT	FILL ADJUSTED FOR SHRINKAGE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE
	CU YARDS	CU YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	SQUARE YARDS
STA 104+00 TO 106+83.42	317	0	---	317	196	+121	788
CULVERT	0	0	---	0	24	-24	0
STA 107+16.58 TO 109+83.42	103	0	---	103	538	-435	833
CULVERT	0	50	---	0	23	-23	0
STA 110+16.58 TO 115+10	579	0	---	579	177	+402	1653
TOTAL	999	50	---	999	956	+43	3274

STAGE I

TEMPORARY PAVEMENT EARTHWORK SCHEDULE							
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED FOR FURNISH EMBANKMENT	FILL ADJUSTED FOR SHRINKAGE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE
	CU YARDS	CU YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	SQUARE YARDS
STA 97+00 TO 106+83.42	326	0	---	326	14	+312	761
CULVERT	10	0	---	10	21	-11	0
STA 107+16.58 TO 109+83.42	172	0	---	172	0	+172	0
CULVERT	3	0	---	3	18	-15	0
STA 110+16.58 TO 122+10	289	0	---	289	128	+161	839
TOTAL	800	0	---	800	180	+620	1600

SWELL FACTOR = 5%

SHRINK FACTOR = 15%

3287EarthworkSchedule.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 U.S. ROUTE 14 OVER LAWRENCE CREEK  
**EARTHWORK SCHEDULE**  
 DRAWN BY CLG  
 CHECKED BY JJD  
 DATE: 2-15-05

