

#62391

STAGE II

EARTHWORK SCHEDULE							
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED FOR FURNISH EMBANKMENT	FILL ADJUSTED FOR SHRINKAGE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE
	CU YARDS	CU YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	SQUARE YARDS
STA 104+00 TO 106+83.42	237	0	---	237	68	+169	613
CULVERT	0	0	---	0	24	-24	0
STA 107+16.58 TO 109+83.42	57	0	---	57	217	-160	406
CULVERT	0	0	---	0	6	-6	0
STA 110+16.58 TO 115+10	233	0	---	233	275	-42	1187
TOTAL	526	0	---	526	590	-64	2206

STAGE II

TEMPORARY PAVEMENT EARTHWORK SCHEDULE							
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED FOR FURNISH EMBANKMENT	FILL ADJUSTED FOR SHRINKAGE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE
	CU YARDS	CU YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	CUBIC YARDS	SQUARE YARDS
STA 98+60 TO 106+83.42	85	0	---	85	0	+85	778
CULVERT	0	0	---	0	0	0	0
STA 107+16.58 TO 109+83.42	0	0	---	0	0	0	0
CULVERT	0	0	---	0	0	0	0
STA 110+16.58 TO 120+50	62	0	---	62	3	+59	754
TOTAL	147	0	---	147	3	+144	1532

SHRINK FACTOR = 15%

3287EarthworkSchedule.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14 OVER LAWRENCE CREEK
EARTHWORK SCHEDULE
DRAWN BY CLG
CHECKED BY JJD
DATE: 2-15-05

