

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-39-	201-1B-M-2	WINNEBAGO	13	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

General Notes

The contractor shall submit four copies of the required shop drawings for review and approval to the Bureau of Bridges and Structures, 2300 South Dirksen Parkway, Springfield, IL 62764. After approval of initial submittal, the contractor shall submit one set of shop drawings to Eric Harm, Engineer of Materials, 126 East Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

- District 2 District Engineer (1)
- Fabricator (1)
- Contractor (2)
- Resident Engineer (2)
- District 2 Bureau of Materials (2)

Work on this project will be in progress at the same time as work on the ROCKFORD BYPASS US 20 (BYP). Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

A contingency item of 10 delineators is included to delineate potential hazards in the project limits. These to be placed upon project completion at the discretion of the engineer.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

- | | | | |
|---|---------------------------|--|---------------------------|
| Mr. Mike Lenox
Commonwealth Edison Company
123 Energy Ave.
Rockford IL 61109 | Electric
815-490-2869 | Mr. Frank Rose
SBC/Ameritech Telephone Co.
2404 Eighth Ave.
Rockford IL 61108 | Telephone
815-394-7276 |
| Mr. Kalin Hinshaw
Verizon
112 West Elm Street
Sycamore IL 60178 | Telephone
815-895-1515 | Mr. Scott Stogsdill
NICOR Gas Co.
1844 Ferry Road
Naperville IL 60563-9600 | Gas
630-983-8676 |
| Mr. Scott Schroeder
Insight Communications
115 N. Galena Ave
Dixon IL 61021 | CATV
815-284-2257 | | |

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

- Mr. Dennis Schultz
IDOT - Dist. 2
819 Depot Ave
Dixon IL 61021
- GOVT
815-284-5469

Summary Of Quantities

Code Number	Pay Item	Unit	Quantity
			SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	20.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20.9
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	39090
50501110	STRUCTURAL STEEL REMOVAL	POUND	23300
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4370
58100100	WATERPROOF MEMBRANE REPAIR	SQ YD	52
63500105	DELINEATORS	EACH	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12796
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5290
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4287.5
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	700
78300100	PAVEMENT MARKING REMOVAL	SQ FT	145
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	6
Z0022400	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	78

* SPECIALTY ITEM

The following Mixture Requirements are applicable for this project:

Mixture Uses(s):	Surface		
PG:	SBS 70-22		
RAP%: (Max)	0%		
Design Air Voids			
Mixture Composition (Gradation Mixture)	IL 9.5 or 12.5		
Friction Aggregate	E		
20 Year ESAL			

Structure No. 101-0133
I-39 over Kishwaukee River
Winnebago County
FAI Route 39
Section 201-1B-M-2