

| | | | | |
|-----------------------|---------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 74 | • | TAZEWELL | 1366 | 11 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 4 | | ILLINOIS FED. AID PROJECT | | |

• (90-11)R-2;90(13,14,14-1)R-1

| SUMMARY OF QUANTITIES FOR ALL PLAN SETS | | | | URBAN | | | | | | | | | | | | |
|--|---|-------|----------------|---------------------------------------|---------------------------------------|---------------------------------|------------------------------|------------------------------|--------------------|----------------------|--------------------|--------------------|-------------------------|------------------------|------------------|-------------------------|
| | | | | IM | | | | | | IM | | | | | | |
| | | | | 90% FED 10% STATE | | | | | | 90% FED 10% STATE | | | | | | |
| | | | | CONSTRUCTION TYPE CODE | | | | | | | | | | | | |
| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | INTERSTATE ROADWAY 3 LANE (1) J000-2A | INTERSTATE ROADWAY 2 LANE (2) J000-2A | INTERSTATE ROADWAY (2A) I000-2A | ARTERIAL ROADWAY (3) I000-2A | ARTERIAL ROADWAY (4) J000-2A | BRIDGE (5) X281-2A | BRIDGE (6) X581-2A | BRIDGE (7) X271-2A | BRIDGE (8) X971-2A | RETAINING WALL (9) Y007 | OVERHEAD SIGNS Y002-1C | LIGHTING Y030-1E | TRAFFIC SIGNALS Y031-1F |
| 28000300 | TEMPORARY DITCH CHECKS | EACH | 95 | 83 | | | 1 | 11 | | | | | | | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 290 | 268 | 22 | | | | | | | | | | | |
| 50100300 | REMOVAL OF EXISTING STRUCTURES NO. 1 | EACH | 1 | | | | | | 1 | | | | | | | |
| 50100400 | REMOVAL OF EXISTING STRUCTURES NO. 2 | EACH | 1 | | | | | | | 1 | | | | | | |
| 50100500 | REMOVAL OF EXISTING STRUCTURES NO. 3 | EACH | 1 | | | | | | 1 | | | | | | | |
| 50104400 | CONCRETE HEADWALL REMOVAL | EACH | 33 | 16 | 11 | | 5 | 1 | | | | | | | | |
| 50104710 | REMOVAL OF EXISTING BEARINGS | EACH | 10 | | | | | | | | | 10 | | | | |
| 50104800 | REMOVAL OF EXISTING CONCRETE DECK | L SUM | 1 | | | | | | | | | 1 | | | | |
| 50300100 | FLOOR DRAINS | EACH | 7 | | | | | | | | | 7 | | | | |
| 50300310 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 12 | | | | | | | | | 12 | | | | |
| 50300320 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 28 | | | | | | | | 4 | 24 | | | | |
| 50300330 | ELASTOMERIC BEARING ASSEMBLY, TYPE III | EACH | 4 | | | | | | | | 4 | | | | | |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 2478 | | | | | | | | 4292 | 12334 | 7232 | | | |
| 50500715 | JACK AND REMOVE EXISTING BEARINGS | EACH | 30 | | | | | | | | | 30 | | | | |
| 50600300 | CLEANING AND PAINTING STEEL BRIDGE | L SUM | 1 | | | | | | | | | 1 | | | | |
| 50606400 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES | L SUM | 1 | | | | | | | | | 1 | | | | |
| 51500100 | NAME PLATES | EACH | 7 | | | | | | 2 | 1 | 1 | 1 | 2 | | | |
| 54244805 | INLET BOX, STANDARD 542501 | EACH | 1 | | 1 | | | | | | | | | | | |
| 54246205 | INLET BOX, STANDARD 542526 | EACH | 1 | | 1 | | | | | | | | | | | |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS | EACH | 29 | 15 | 12 | | 2 | | | | | | | | | |
| 60240301 | INLETS, TYPE B, TYPE 8 GRATE | EACH | 1 | 1 | | | | | | | | | | | | |
| 60240303 | INLETS, TYPE B, TYPE 9 FRAME AND GRATE | EACH | 3 | 3 | | | | | | | | | | | | |
| 60240324 | INLETS, TYPE B, TYPE 20 FRAME AND GRATE | EACH | 2 | 2 | | | | | | | | | | | | |
| 60241900 | INLETS, TYPE G-1, SPECIAL | EACH | 61 | 2 | | | 38 | 21 | | | | | | | | |
| 60242400 | INLETS, SPECIAL | EACH | 7 | | 7 | | | | | | | | | | | |
| 60247132 | DRAINAGE STRUCTURES, TYPE 1A WITH ONE TYPE 20 FRAME AND GRATE | EACH | 15 | 15 | | | | | | | | | | | | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 7 | | | | | 7 | | | | | | | | |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 1 | | | | 1 | | | | | | | | | |
| 60260500 | INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE | EACH | 7 | | | | | 7 | | | | | | | | |
| 60403400 | GRATES, TYPE A | EACH | 5 | | 5 | | | | | | | | | | | |
| 60500040 | REMOVING MANHOLES | EACH | 2 | | | | 2 | | | | | | | | | |
| 60500060 | REMOVING INLETS | EACH | 40 | 30 | 9 | | | 1 | | | | | | | | |
| 60500105 | FILLING MANHOLES | EACH | 2 | | | | | 2 | | | | | | | | |
| 60500305 | FILLING INLETS | EACH | 2 | | | | | 2 | | | | | | | | |
| 60603300 | GUTTER OUTLET | EACH | 3 | | 3 | | | | | | | | | | | |
| 60900215 | TYPE C INLET BOX, STANDARD 609001 | EACH | 5 | 4 | 1 | | | | | | | | | | | |

- △ SFTY-3N
- SFTY-3C
- Y080
- ∅ NON-PARTICIPATING

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)



| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY _____

CHECKED BY _____

02/14/2005 11:22:49 AM

CONTRACT # 017705