

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	17
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

\* (90-111R-2)9013,14,14-1R-1

SUMMARY OF QUANTITIES FOR ALL PLAN SETS				URBAN												
				IM						IM						
				90% FED 10% STATE						90% FED 10% STATE						
				CONSTRUCTION TYPE CODE												
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	INTERSTATE ROADWAY (2A) I000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581-2A	BRIDGE (7) X211-2A	BRIDGE (8) X971-2A	RETAINING WALL (9) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
M5500070	STORM SEWERS, CLASS A, TYPE 1 675MM	METER	6.0				6.0									
M5500075	STORM SEWERS, CLASS A, TYPE 1 750MM	METER	77.0	63.5			3.0	10.5								
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	364.0	104.0			260.0									
M5500450	STORM SEWERS, CLASS A, TYPE 2 450MM	METER	189.5				162.5	27.0								
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	1056.0	511.5	408.5		136.0									
M5500475	STORM SEWERS, CLASS A, TYPE 2 750MM	METER	128.0				124.0	4.0								
M5500485	STORM SEWERS, CLASS A, TYPE 2 900MM	METER	38.5		38.5											
M5500495	STORM SEWERS, CLASS A, TYPE 2 1050MM	METER	15.0		15.0											
M5500515	STORM SEWERS, CLASS A, TYPE 2 1650MM	METER	45.5		45.5											
M5500830	STORM SEWERS, CLASS A, TYPE 3 300MM	METER	64.5				64.5									
M5500865	STORM SEWERS, CLASS A, TYPE 3 600MM	METER	42.5	42.5												
M5500875	STORM SEWERS, CLASS A, TYPE 3 750MM	METER	161.0		161.0											
M5501230	STORM SEWERS, CLASS A, TYPE 4 300MM	METER	17.5				17.5									
M5501275	STORM SEWERS, CLASS A, TYPE 4 750MM	METER	16.5				16.5									
M5510025	STORM SEWER REMOVAL 300MM	METER	20.5		11.0			9.5								
M5510035	STORM SEWER REMOVAL 375MM	METER	31.0		31.0											
M5510040	STORM SEWER REMOVAL 400MM	METER	46.0	46.0												
M5510060	STORM SEWER REMOVAL 600MM	METER	45.5	37.0			8.5									
M5510070	STORM SEWER REMOVAL 750MM	METER	42		39			2.5								
M5510080	STORM SEWER REMOVAL 900MM	METER	7				6.5									
M5510105	STORM SEWER REMOVAL 1500MM	METER	1		1											
M5510110	STORM SEWER REMOVAL 1650MM	METER	2		2											
M5870020	BRIDGE SEAT SEALER	SQ M	115								42	73				
M5900100	EPOXY CRACK SEALING	METER	34									34				
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	781										781			
M6010080	FRENCH DRAINS	CU M	29										29			
M6010125	PIPE DRAINS 300MM	METER	256	218.5	37											
M6010130	PIPE DRAINS 375MM	METER	11		10.5											
M6010135	PIPE DRAINS 450MM	METER	122		122											
M6010605	PIPE UNDERDRAINS 100MM	METER	3433	973	2459.5											
M6010610	PIPE UNDERDRAINS 150MM	METER	153.0		128.5		24.5									
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	1502.0	1435.0	67.0											
M6010710	PIPE UNDERDRAINS 150MM (SPECIAL)	METER	2.0		2.0											
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3.0		2.0		1.0									
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	21.0	1.0	3.0		14.0	3.0								
M6021445	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 9 FRAME AND GRATE	EACH	2.0	2.0												

- △ SFTY-3N
- SFTY-3C
- Y080
- NON-PARTICIPATING

- (1) I-74 STA. 152+445.837 TO STA. 153+892.180
- (2) I-74 STA. 153+892.180 TO STA. 154+970.000
- (2A) I-74 EB STA. 154+780.000 TO STA. 157+666.230 & I-74 WB STA. 154+952.000 TO STA. 157+666.230
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000, MAIN STREET STA. 2+402.933 TO STA. 2+800.000, & WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000
- (5) BRIDGE PLANS SN 090-0160 (SN 090-0006) (WB I-74 OVER MAIN STREET) & BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)

- (6) BRIDGE PLANS SN 090-0159 (SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (7) BRIDGE PLANS SN 090-0156 (SN 090-0010 EB & SN 090-0011 WB) (RAMP K-2 OVER MAIN STREET AND RAMP J-3)
- (8) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (9) RETAINING WALL SN 090-8512 (ALONG RAMP J-3) RETAINING WALL SN 090-8513 (ALONG RAMP K-2)



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 02/14/2005

DRAWN BY  
CHECKED BY

02/14/2005 11:22:52 AM  
91:\data\5589-74\dwg\contract\packaging\eq107d-6a.dgn

CONTRACT IN PACKAGING PAGE 17 OF 25 FINAL PLANS 01/17/05