

11/17/2004 10:11:18 AM 68201

68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\*90-IDR-2;90I13,14,14-IDR-1

**BILL OF MATERIALS FOR SET 1 OF 4**  
**FOR INFORMATION ONLY**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN										
				IM 90% FED 10% STATE		BRI 80% FED 20% STATE		IM 90% FED 10% STATE						
				CONSTRUCTION TYPE CODE										
				INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) 1000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F		
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	377	377										
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	377	377										
M2500700	AGRICULTURAL GROUND LIMESTONE	M TON	21.0	21.0										
M2510115	MULCH, METHOD 2	HA	4.0	4.0										
M2510630	EROSION CONTROL BLANKET	SQ M	39120	39120										
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	12713	12713										
M2800400	PERIMETER EROSION BARRIER	METER	5303	5303										
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	551	551										
M2820100	FILTER FABRIC FOR USE WITH RIPRAP	SQ M	551	551										
M2850300	ARTICULATED BLOCK MAT	SQ M	362	362										
M3511100	AGGREGATE BASE COURSE, TYPE B 100MM	SQ M	520	520										
M3530250	PORTLAND CEMENT CONCRETE BASE COURSE 250MM	SQ M	10055		10055									
M3540250	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 250MM	SQ M	525		525									
M4060085	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ M	137		137									
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	64797	46106	18691									
M4060300	AGGREGATE (PRIME COAT)	M TON	112		112									
M4060980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ M	202		202									
M4060990	TEMPORARY RAMP	SQ M	58		58									
M4080400	INCIDENTAL BITUMINOUS SURFACING	M TON	3		3									
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	17238	4650	12588									
M4205000	BRIDGE APPROACH PAVEMENT	SQ M	727	727										
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	439	439										
M4205100	PAVEMENT FABRIC	SQ M	10055		10055									

SHEET 4 OF 15

- |  |  |
|--|--|
| (1) WB I-74 STA 152+445.837 TO STA 153+892.180 | (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)<br>BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET) |
| (2) MAIN STREET STA 2+800.000 TO STA 4+157.000 | (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)   |
| (3) MAIN STREET STA 2+402.933 TO STA 2+800.000 | (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)<br>(7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)      |
|  | (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)<br>RETAINING WALL SN 090-8513 (ALONG RAMP K-2)   |



REVISIONS	
NAME	DATE

**ILLINOIS DEPARTMENT OF TRANSPORTATION**  
**FAI ROUTE 74 (I-74)**  
**TOTAL BILL OF MATERIALS**  
 DATE 12-20-04  
 DRAWN BY MLS  
 CHECKED BY JJM