

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	TAZEWELL	1366	41
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*90-11R-2;90(13,14,14-DR-1

BILL OF MATERIALS FOR SET 1 OF 4
FOR INFORMATION ONLY

					URBAN									
					IM 90% FED 10% STATE		BRI 80% FED 20% STATE			IM 90% FED 10% STATE				
					CONSTRUCTION TYPE CODE									
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY		INTERSTATE ROADWAY 3 LANE (1) J000-2A	ARTERIAL ROADWAY (2) I000-2A	ARTERIAL ROADWAY (3) J000-2A	BRIDGE (4) X281-2A	BRIDGE (5) X581-2A	BRIDGE (6) X281-2A	BRIDGE (7) X971-2A	RETAIN WALL (8) Y007	TRAFFIC SIGNALS Y031-1F	
MX509025	ALUMINUM RAILING, TYPE H, SPECIAL	METER	117.0					117.0						
MX602751	INLET-MANHOLE, TYPE G-1, 1.2M DIAMETER, SPECIAL	EACH	5			5								
MX602756	INLET-MANHOLE, TYPE G-1, 1.5M DIAMETER, SPECIAL	EACH	22			20	2							
MX637112	CONCRETE BARRIER TRANSITION (MODIFIED)	METER	10		10									
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	832.65		832.65									
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	32.3		32.3									
MX721010	COMPOSITE TEMPORARY SIGN OVERLAY	SQ M	22		22									
MX871055	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	METER	1516.0										1516.0	
MX877017	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 15.85 METER	EACH	1										1	
MX877020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.76 METER	EACH	3										3	
MX878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	25										25	
MZ008830	DRILLED SHAFT IN SOIL, 915MM	METER	25.5							25.5				
MZ008880	DRILLED SHAFT IN SOIL, 1830MM	METER	1.0							1.0				
MZ008930	DRILLED SHAFT IN ROCK, 760MM	METER	20.5							20.5				
MZ008980	DRILLED SHAFT IN ROCK, 1830MM	METER	16.5							16.5				
MZ017205	DOWEL BARS 38MM	EACH	1133		21	1112								
MZ022400	FABRIC REINFORCED ELASTOMERIC TROUGH	METER	36.9							17.5	19.4			
MZ047300	PROTECTIVE SHIELD	SQ M	2959				1099	310			1550			
X0301840	DRILL AND GROUT #35 TIE BARS	EACH	1308		196	1112								
X0321809	PERMANENT GROUND ANCHOR	EACH	204									204		
X0323481	VIDEO VEHICLE DETECTION, 4 CAMERAS	EACH	2										2	
X0323639	INSTALL BOLLARD AND LUMINAIRES	EACH	4				4							

SHEET 13 OF 15

- (1) WB I-74 STA 152+445.837 TO STA 153+892.180
- (2) MAIN STREET STA 2+800.000 TO STA 4+157.000
- (3) MAIN STREET STA 2+402.933 TO STA 2+800.000

- (4) BRIDGE PLANS SN 090-0160 (EX SN 090-0006) (WB I-74 OVER MAIN STREET)
BRIDGE PLANS SN 090-0163 (EX SN 090-0011) (WB I-74 OVER WASHINGTON STREET)
- (5) BRIDGE PLANS SN 090-0159 (EX SN 090-0005) (WB I-74 OVER ALTORFER LANE AND TP&W RAILROAD)
- (6) BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- (7) BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND TP&W RAILROAD)
- (8) RETAINING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)

TOTAL BILL OF MATERIALS

DATE 12-20-04

DRAWN BY MLS
CHECKED BY JJM

11/13/04 10:58 AM 01/17/2005 04:47:26 PM