

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	190-1R-29013,14,14-1R-1	TAZEWELL	1366	94
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		

TRAFFIC PROTECTION SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 2 (EACH)	TERMINAL MARKERS - DIRECT APPLIED (EACH)	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2 (EACH)	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3 (EACH)
MAINLINE 153+202.437 LT		1		1
RAMP J-3 10+235.516 LT		1		1
RAMP J-4 10+119.600 RT		1		1
RAMP K-2 10+064.344 RT 10+101.030 LT 10+370.000 RT	1	1	1	
TOTAL	* 1	5	2	3

CURB AND GUTTER SCHEDULE

LOCATION	CLASS SI CONC OUTLET (CU M)	CONCRETE GUTTER TYPE A (METER)	CONCRETE GUTTER TYPE A (MODIFIED) (METER)	CONCRETE CURB & GUTTER B-15.45 (METER)
RAMP J-3 10+145.073 TO 10+235.516 LT 10+250.000 TO 10+275.000 RT STA. 10+275.000 RT	2.7		90.4 25.0	
RAMP J-4 10+065.000 TO 10+322.209 LT			257.2	
RAMP K-2 10+052.874 TO 10+085.874 10+085.874 TO 10+178.600 RT 10+344.000 TO 10+378.450 RT 10+378.450 TO 10+507.550 RT		139.6	92.7 34.4	33.0
TOTAL	* 2.7	* 139.6	499.7	33.0

DUST CONTROL

LOCATION	STREET SWEEPING (HOUR)	APPLY DUST SUPPRESSION AGENTS (UNIT)	SOIL STABILIZER (KG)	DUST CONTROL PADS (EACH)
MAINLINE 152+445.837 TO 152+700.000 152+700.000 TO 153+000.000 153+000.000 TO 153+300.000 153+300.000 TO 153+600.000 153+600.000 TO 153+892.180	52	70	1350	4
RAMP J-3	49	69	1350	4
RAMP J-4	49	68	4500	4
RAMP K-2 10+052.874 TO 10+352.500 10+352.500 TO 10+654	52	70	1350	4
TOTAL	* 462	* 627	* 13500	* 36

CONCRETE SHALE CAP SCHEDULE

LOCATION	CLASS SI CONCRETE SPECIAL (CU M)
RAMP J-3 STA. 10+175 TO 10+350	154.2
TOTAL	154.2

ESTIMATED LIMITS WHERE SHALE MAY BE ENCOUNTERED PER GEOTECHNICAL SOILS REPORT

* NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD

CHAIN LINK FENCE SCHEDULE

STATION	TO	STATION	CHAIN LINK FENCE 1.2 METER (METER)
MAINLINE 153+750.100, 14.3M LT	TO	153+827.930, 14.3M LT	121.0
RAMP J-4 10+332.000, 25.3M RT	TO	10+332.580, 3.9M RT	21.4
10+387.110, 25.2M RT	TO	10+387.820, 3.9M RT	21.3
TOTAL			* 163.7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 I-74 WB
 RAMPS J-3 & J-4



DATE 12-20-04
 DRAWN BY CGF
 CHECKED BY RLS

No. 01, SEC. 3, P. 002/22/21, ufp, qms-101114, 1/28/04, 1/28/04

DATE: DATE-A TIME HERE: TIME HERE: \$DGN FILE NAME GOES HERE-SIZE IS LARGE ENOUGH FOR LONG FILE NAMES