

**PAVEMENT MARKING SCHEDULE**

68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	190-10R-22003,14,14-1R-1	TAZEWELL	1366	95
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

LOCATION EASTBOUND	TYPE	POLYUREA LINE 100MM		POLYUREA LINE 150MM WHITE (METER)	POLYUREA LINE 200MM WHITE (METER)	POLYUREA LINE 300MM WHITE (METER)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)
		WHITE (METER)	YELLOW (METER)				
<b>MAINLINE EASTBOUND</b>							
151+620.154 TO 151+850.000	SKIP-DASH SOLID	230	230	84			15
	DOTTED				30		
151+850.000 TO 152+150.000	SKIP-DASH SOLID	183	300	171	118		41
152+150.000 TO 152+445.837	SKIP-DASH SOLID	296	296	216			36
152+445.837 TO 152+700.000	SKIP-DASH SOLID		254	132	163		37
152+700.000 TO 153+000.000	SKIP-DASH SOLID	57	300	150	173		44
	DOTTED				16		
153+000.000 TO 153+300.000	SKIP-DASH SOLID	295	300	93	5		23
	DOTTED				40		
153+300.000 TO 153+600.000	SKIP-DASH SOLID		300	75	300		35
153+600.000 TO 153+892.180	SKIP-DASH SOLID	247	292	132	45		30
	DOTTED				12		
<b>RAMP J-1</b>							
10+068.624 TO 10+231.824	SKIP-DASH SOLID			58	163		23
	DIAGONALS					68	
10+231.824 TO 10+255.242	SOLID				24		
	DIAGONALS					22	
<b>RAMP K-1</b>							
10+068.808 TO 10+161.937	SOLID				93		8
	DIAGONALS					29	
<b>RAMP J-2</b>							
10+242.470 TO 10+248.000	SOLID				5		
	DIAGONALS					7	
10+248.000 TO 10+530.853	SOLID				280		23
	DIAGONALS					100	
<b>WESTBOUND</b>							
<b>MAINLINE</b>							
152+150.000 TO 152+445.837	SKIP-DASH SOLID	203	296	181	90		37
152+445.837 TO 152+700.000	SKIP-DASH SOLID	65	254	143	189		39
152+700.000 TO 153+000.000	SKIP-DASH SOLID	155	300	84	260		34
153+000.000 TO 153+300.000	SKIP-DASH SOLID	284	300	72	16		23
	DOTTED				33		
153+300.000 TO 153+600.000	SKIP-DASH SOLID	246	300	138	54		39
	DOTTED				30		
153+600.000 TO 153+892.180	SKIP-DASH SOLID	257	292	117	100		28
<b>RAMP H-3</b>							
10+000.000 TO 10+161.620	SKIP-DASH SOLID	162		41	90		14
	DIAGONALS					24	
<b>RAMP J-4</b>							
10+065.000 TO 10+345.000	SOLID	280	257		24		2
10+345.000 TO 10+534.716	SOLID	190			190		16
<b>RAMP K-2</b>							
10+052.874 TO 10+352.500	SOLID	300	300				
10+352.500 TO 10+653.500	SOLID	301	301				
10+653.500 TO 10+848.862	SOLID	146	31		164		13
<b>RAMP J-3</b>							
10+074.856 TO 10+129.000	SOLID	54			54		14
	DIAGONALS					20	
10+129.000 TO 10+350.000	SKIP-DASH SOLID	221	205	9	16		
	DIAGONALS					16	
<b>RAMP L-4</b>							
	SOLID	35			35		3
<b>SUBTOTAL TOTAL</b>		<b>4207</b>	<b>5108</b>	<b>1896</b>	<b>*2812</b>	<b>286</b>	<b>577</b>
		<b>*9315</b>					

\*NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)

DATE: DATE/TIME HERE: TIME HERE: \$0.00 FILE NAME GOES HERE: SIZE IS LARGE ENOUGH FOR LONG FILE NAMES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES I-74 WB RAMPS J-3 & J-4 DRAWN BY CGF CHECKED BY RLS DATE 12-20-04
NAME	DATE	

