

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	97
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\*(90-11R-2;90(13,14,14-1R-1

**PAVEMENT REMOVAL**

LOCATION	( SO M ) ( DEPTH = ±325mm)
<b>MAIN STREET</b>	
STA 2+402.933 TO 2+450.000	1144
STA 2+450.000 TO 2+600.000	3291
STA 0+048 TO 0+109 (RAMP 18)	280
STA 5+130 TO 5+199 (RAMP 19)	261
STA 6+012 TO 6+055 (RAMP 20)	642
STA 7+232 TO 7+281 (RAMP 21)	591
STA 2+600.000 TO 2+750.000	3027
STA 2+750.000 TO 2+800.000	1089
RT STA 2+864.000 TO 2+900.000	17
RT STA 2+900.000 TO 2+930.000	19
<b>SIDERoadS</b>	
ALTORFER ROAD AND FRONTAGE ROAD	1071
NATIONAL STREET	595
CATERPILLAR TRAIL	190
BLACKJACK BLVD (WEST LEG)	611
BLACKJACK BLVD (EAST LEG)	572
<b>TOTAL</b>	<b>** 13400</b>

**DRIVEWAY PAVEMENT REMOVAL**

LOCATION	( SO M ) ( DEPTH = ±200mm)
<b>MAIN STREET</b>	
CE RT STA 2+664.751	133
CE RT STA 2+705.459	87
CE RT STA 2+738.536	45
PE RT STA 3+993.559	67
PE RT STA 4+073.830	84
PE RT STA 4+119.318	36
<b>TOTAL</b>	<b>** 452</b>

**MISCELLANEOUS REMOVAL SCHEDULE**

LOCATION	SIDEWALK ( SO M ) ( DEPTH = ±100mm)	ISLAND ( SO M ) ( DEPTH = ±625mm)	MEDIAN ( SO M ) ( DEPTH = ±625mm)	GUARD RAIL ( METER )
<b>MAIN STREET</b>				
RT STA 2+440.200 TO 2+450.000	10			
STA 2+402.933 TO 2+415.933				38
LT STA 5+130.000 TO 5+138.000 (RAMP 19)				14
RT STA 7+295.000 TO 7+367.000 (RAMP 21)				55
STA 2+556.000 TO 2+600.000				108
RT STA 2+450.000 TO 2+520.000	78			
RT STA 0+109.000 (RAMP 18) TO 2+600.000				119
RT STA 6+099.000 TO 6+123.000 (RAMP 20)				24
STA 2+600.000 TO 2+618.410				48
LT STA 2+600.000 TO 2+654.000				54
LT STA 2+690.000		22		
RT STA 2+789.000	5			
RT STA 2+852.000	9			
LT STA 2+930.000		14		
RT STA 3+737.000		42		
RT STA 3+750.300 TO 3+792.600				42
<b>BLACKJACK BLVD</b>				
STA 99+909.000 TO 99+939.000				56
<b>TOTALS</b>	<b>** 102</b>	<b>** 78</b>	<b>** 319</b>	<b>* 239</b>

**PAVED SHOULDER REMOVAL**

LOCATION	TYPE	( SO M ) ( DEPTH = ±250mm)
<b>MAIN STREET</b>		
LT STA 5+130.000 TO 5+191.000 (RAMP 19)	BIT	115
RT STA 0+056.000 TO 0+109.000 (RAMP 18)	BIT	94
LT STA 0+056.000 (RAMP 18) TO 2+600.000	CONC	137
RT STA 2+520.000 TO 6+055.000 (RAMP 20)	BIT	127
RT STA 2+533.000 TO 7+257.000 (RAMP 21)	BIT	182
LT STA 6+055.000 TO 6+123.000 (RAMP 20)	BIT	143
RT STA 7+281.000 (RAMP 21) TO 2+600.000	BIT	95
RT STA 7+281.000 TO 7+367.000 (RAMP 21)	BIT	171
LT STA 2+600.000 TO 2+675.000	CONC	146
RT STA 2+600.000 TO 2+700.000	BIT	289
LT STA 399+965.000 (ALTORFER ST) TO 2+750.000	BIT	32
RT STA 2+711.000 TO 2+750.000	BIT	117
LT STA 2+750.000 TO 2+807.000	BIT	84
LT STA 2+807.000 TO 2+900.000	CONC	182
RT STA 2+750.000 TO 2+900.000	BIT	308
LT STA 2+900.000 TO 2+908.000	CONC	23
RT STA 2+900.000 TO 2+938.000	BIT	34
RT STA 2+951.000 TO 3+050.000	BIT	308
LT STA 2+965.000 TO 3+050.000	CONC	122
LT STA 3+050.000 TO 3+200.000	CONC	325
RT STA 3+050.000 TO 3+160.000	BIT	311
RT STA 3+160.000 TO 3+200.000	CONC	94
LT STA 3+200.000 TO 3+350.000	CONC	375
RT STA 3+200.000 TO 3+350.000	CONC	365
LT STA 3+350.000 TO 3+500.000	CONC	364
RT STA 3+350.000 TO 3+500.000	CONC	346
LT STA 3+500.000 TO 3+650.000	CONC	357
RT STA 3+500.000 TO 3+650.000	BIT	391
LT STA 3+650.000 TO 3+693.000	CONC	97
RT STA 3+650.000 TO 3+717.000	BIT	93
LT STA 3+750.000 TO 3+800.000	CONC	73
RT STA 3+752.000 TO 3+800.000	BIT	139
RT STA 100+025.000 TO 100+036.000 (BLACKJACK BLVD)	BIT	33
LT STA 100+027.000 TO 100+036.000 (BLACKJACK BLVD)	BIT	18
LT STA 3+800.000 TO 3+950.000	CONC	297
RT STA 3+800.000 TO 3+950.000	BIT	438
LT STA 3+950.000 TO 4+100.000	CONC	354
RT STA 3+950.000 TO 4+100.000	BIT	359
STA 4+013.000 TO 4+100.000	BIT	117
LT STA 4+100.000 TO 4+157.000	CONC	131
RT STA 4+100.000 TO 4+157.000	BIT	140
STA 4+100.000 TO 4+162.000	BIT	156
<b>TOTAL</b>		<b>** 8082</b>

**BITUMINOUS SURFACE REMOVAL**

LOCATION	25mm ( SO M )	50mm ( SO M )
<b>MAIN STREET</b>		
STA 2+800.000 TO 2+900.000	2108	
STA 2+900.000 TO 3+050.000	3301	
STA 3+050.000 TO 3+200.000	2616	
STA 3+200.000 TO 3+350.000	2385	
STA 3+350.000 TO 3+500.000	2407	
STA 3+500.000 TO 3+650.000	2713	
STA 3+650.000 TO 3+800.000	3468	
STA 3+800.000 TO 3+950.000	2788	
STA 3+950.000 TO 4+100.000	2446	
STA 4+100.000 TO 4+148.000	697	
<b>ALTORFER FRONTAGE ROAD</b>		
STA 9+960.332 TO 9+963.332		21
<b>TOTAL</b>	<b>24929</b>	<b>21</b>

\* NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)

\*\* THE REMOVAL QUANTITIES ARE PROVIDED FOR INFORMATIONAL PURPOSES ONLY AND THE REMOVAL ITEMS SHOWN ARE TO BE PAID FOR AS SPECIAL EXCAVATION.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 74 (I-74)  
**SCHEDULE OF QUANTITIES**  
MAIN STREET  
RAMPS J-3 & J-4  
DRAWN BY SRS  
CHECKED BY JMM  
DATE 12-20-04



\\phase2\roadway\st101\sham.dgn 12/21/2004 7:48:32 AM