

*(90-11)R-2;90(13,14,14-1)R-1

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	99
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC						EPOXY										
		LETTERS AND SYMBOLS (SQ M)	LINE 100MM		LINE 150MM WHITE (METER)	LINE 200MM WHITE (METER)	LINE 300MM		LETTERS AND SYMBOLS (SQ M)	LINE 100MM		LINE 150MM WHITE (METER)	LINE 200MM WHITE (METER)	LINE 300MM		LINE 600MM WHITE (METER)		
			WHITE (METER)	YELLOW (METER)			WHITE (METER)	YELLOW (METER)		WHITE (METER)	YELLOW (METER)			WHITE (METER)	YELLOW (METER)			
MAIN STREET																		
2+218.898 TO 2+550.000 (INCLUDING FON DU LAC DRIVE)	9M-3M SKIP-DASH 15-LT OR RT ARROWS TURN LANES MEDIANS STOP LINES DOTTED		9					22.05			216							
2+550.000 TO 2+900.000 (INCLUDING ALTORFER LANE)	9M-3M SKIP-DASH 7-LT OR RT ARROWS TURN LANES SOLID DBL SOLID MEDIANS STOP LINES DIAGONALS DOTTED ISLANDS	1.47		108				8.82	18		228							
2+900.000 TO 3+250.000 (INCLUDING NATIONAL STREET)	9M-3M SKIP-DASH 4-LT OR RT ARROWS TURN LANES MEDIANS STOP LINES DIAGONALS DOTTED	5.88	6	342						64					35			
3+250.000 TO 3+600.000	9M-3M SKIP-DASH 1-TURN ARROW TURN LANES MEDIAN DBL SOLID DIAGONALS DOTTED	1.47			85													
3+600.000 TO 3+950.000	9M-3M SKIP-DASH 13-LT OR RT ARROWS TURN LANES DBL SOLID MEDIAN STOP LINES CROSSWALK DIAGONALS DOTTED	19.11		312		312			119									
3+950.000 TO 4+157.000	9M-3M SKIP-DASH MEDIAN DIAGONALS																	
BLACKJACK BOULEVARD (WEST LEG) (INCLUDING FRONTAGE ROAD)	9M-3M SKIP-DASH 6-LT OR RT ARROWS TURN LANES DBL SOLID MEDIAN DIAGONALS STOP LINES DOTTED ISLANDS	8.82	6	33		150												
BLACKJACK BOULEVARD (EAST LEG)	4-LT OR RT ARROWS TURN LANES MEDIAN DIAGONALS STOP LINES DOTTED ISLAND	5.88				34												
RAMP J-3	2-LT OR RT ARROWS							2.94										
TOTALS		42.63	41	5337	1263	785		19	539	85	33.81	82	948	444	472	35	46	93
				5378				558				1030			81			

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	POLYUREA - TYPE I			
		LINE 100MM		LINE 200MM WHITE (METER)	LINE 600MM WHITE (METER)
		WHITE (METER)	YELLOW (METER)		
RAMP J-3 STA. 10+350 TO MAIN ST.	SOLID STOP LINES EDGE LINES			15	11
RAMP J-4 MAIN ST. TO STA. 10+065	EDGE LINES	15	49		
TOTALS		20	64	*15	11
		*84			

* NOT A TOTAL QUANTITY
(FOR TOTAL QUANTITY ADD
SIMILAR PAY ITEMS)



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)
SCHEDULE OF QUANTITIES
MAIN STREET
RAMPS J-3 & J-4
DRAWN BY SRS
CHECKED BY JMM
DATE 12-20-04