68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	100
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* (90-1)R-2;90(3,4,4-1)R-1

R. O. W. MARKERS

LOCATION	EACH
MAIN STREET	
26.691M LT. STA. 2+682.586	1
40.616M LT. STA. 2+682.692	1
50.594M LT. STA. 2+694.207	1
62.393M LT. STA. 2+694.592	1
62.232M LT. STA. 2+706.618	1
25.230M LT. STA. 2+714.012	1
27.450M LT. STA. 2+920.235	1
41.338M LT. STA. 2+931.808	1
41.228M LT. STA. 2+944.862	1
27.450M LT. STA. 2+955.440	1
TOTAL	10

PERMANENT SURVEY MARKERS

LOCATION	TYPE 1 (EACH)
MAIN STREET	
PI STA 2+579.299	1
POT STA 2+900.000	1
POT STA 3+200.000	1
POT STA 3+500.000	1
POT STA 3+800.000	1
PC STA 4+038.852	1
PI STA 4+095.543	1
PT STA 4+152.181	1
TOTAL	* 8

DUST CONTROL SCHEDULE

LOCATION	STREET SWEEPING (HOUR)	APPLY DUST SUPPRESSION AGENTS (UNIT)	SOIL STABILIZERS (KG)	DUST CONTROL PADS (EACH)
MAIN STREET				
2+300 TO 2+450.000	7	12	405	1
2+450.000 TO 2+600.000	23	108	3330	2
2+600.000 TO 2+750.000	24	26	1449	2
2+750.000 TO 2+900.000	23	45	2676	2
2+900.000 TO 3+050.000	24	33	1512	2
3+050.000 TO 3+200.000	23	52	2757	2
3+200.000 TO 3+350.000	24	48	2568	2
3+350.000 TO 3+500.000	23	43	1727	2
3+500.000 TO 3+650.000	24	30	1767	2
3+650.000 TO 3+800.000	23	37	1952	2
3+800.000 TO 3+950.000	24	33	1904	2
3+950.000 TO 4+100.000	23	20	925	2
4+100.000 TO 4+157.000	9	5	211	1
BLACKJACK BOULEVARD	31	6	135	2
TOTALS	* 305	* 498	* 23318	* 26

BUTT JOINT SCHEDULE

LOCATION	PCC SURF REMOVAL (SQ M)	BIT SURF REMOVAL (SQ M)	TEMP RAMP (SQ M)
MAIN STREET			
LT STA 4+157.000		66	11
RT STA 4+157.000		67	11
BLACKJACK BLVD			
LT STA 99+885.450	66		11
RT STA 99+885.450	71		12
FRONTAGE ROAD AT BLACKJACK BLVD			
STA 10+030.825		69	13
TOTALS	137	202	58

* NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)

REVISIONS	
NAME	DATE

URS
URS CORPORATION
DECATUR, ILLINOIS

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 74 (I-74)

SCHEDULE OF QUANTITIES
MAIN STREET
RAMPS J-3 & J-4

DRAWN BY SRS
DATE 12-20-04
CHECKED BY JJM

...\phase2\rd06ky\sh11101-5sma.dgn 12/21/2004 7:51:04 AM