

68201				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	101
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*(90-11R-2;90(13,14,14-1R-1				

**CURB AND GUTTER, SIDEWALK, ISLAND AND MEDIAN SCHEDULE**

LOCATION	CONC GUTTER TYPE A (METER)	COMB CONC CURB & GUTTER				CONC MED SURF 100mm (SQ M)	MEDIAN		CLASS S1 CONC OUTLET (CU M)	PC CONC SIDEWALK 100mm (SQ M)
		B-15.30 (METER)	B-15.60 (METER)	M-15.15 (METER)	M-15.60 (METER)		SB-15.30 (SQ M)	TY-SM (SQ M)		
<b>MAIN STREET</b>										
STA 2+464.000 TO 2+600.000		281				1065				
STA 2+600.000 TO 2+643.410		87				264				
STA 2+643.410 TO 2+688.000							145			
LT STA 2+402.933 TO 2+450.000			47							
RT STA 2+402.933 TO 2+450.000			47						36	
LT STA 2+450.000 TO 2+464.420			14							
RT STA 2+450.000 TO 2+454.738			5							
RT STA 2+482.891 TO 2+600.000			117							
LT STA 2+494.939 TO 2+600.000			105							
RT STA 2+600.000 TO 2+750.000			150							
LT STA 2+600.000 TO 2+673.650			74							
LT STA 2+728.020 TO 2+750.000			22							
LT STA 2+750.000 TO 2+900.000			150							
RT STA 2+750.000 TO 2+900.000			150							
LT STA 2+900.000 TO 2+908.681			9							
RT STA 2+900.000 TO 2+932.710			33							
RT STA 2+952.652 TO 3+050.000			97							
LT STA 2+968.032 TO 2+050.000			82							
LT STA 3+050.000 TO 3+200.000			150							
RT STA 3+050.000 TO 3+200.000			150							
LT STA 3+200.000 TO 3+350.000			150							
RT STA 3+200.000 TO 3+350.000			150							
LT STA 3+350.000 TO 3+500.000			150							
RT STA 3+350.000 TO 3+500.000			150							
LT STA 3+500.000 TO 3+650.000			150							
RT STA 3+500.000 TO 3+650.000			150							
LT STA 3+650.000 TO 3+675.206			25							
RT STA 3+650.000 TO 3+707.351			57							
<b>ISLAND AT BLACKJACK BLVD</b>										
LT STA 3+751.425 TO 3+800.000			49	10	11	17		12		
RT STA 3+761.054 TO 3+800.000			39							
LT STA 3+800.000 TO 3+950.000			150							
RT STA 3+800.000 TO 3+950.000			150							
LT STA 3+950.000 TO 4+100.000			150							
RT STA 3+950.000 TO 4+100.000			150							
LT STA 4+100.000 TO 4+153.400			53						0.5	
RT STA 4+100.000 TO 4+153.400			53						0.5	
<b>SIDERoads</b>										
<b>ALTORFER LANE AND FRONTAGE ROAD AT MAIN STREET</b>										
LT STA 399+938.180 TO 2+728.020 (MAIN ST)			57							
RT STA 399+938.180 TO LT 9+963.333 (FRONTAGE RD)			53							
RT STA 9+963.333 (FRONTAGE RD) TO LT 2+673.650 (MAIN ST)			32							
<b>NATIONAL STREET</b>										
LT STA 199+958.700 TO 2+968.032 (MAIN ST)			42							
RT STA 199+958.700 TO LT 2+908.681 (MAIN ST)			42							
<b>CATERPILLAR TRAIL</b>										
RT STA 2+932.710 (MAIN ST) TO 200+022.531			16							
RT STA 2+952.652 (MAIN ST) TO LT 200+021.400			17							
<b>BLACKJACK BLVD (WEST LEG)</b>										
STA 99+874.650 TO 99+876.450										
RT STA 99+938.143 TO LT 3+675.206 (MAIN ST)			79					11		
LT STA 99+967.649 TO 3+751.425 (MAIN ST)			26							
<b>FRONTAGE ROAD AT BLACKJACK BLVD (WEST LEG)</b>										
LT STA 99+924.220 (BLACKJACK BLVD) TO 10+030.741			36							
LT STA 99+967.649 (BLACKJACK BLVD) TO RT 10+030.908			30							
<b>BLACKJACK BLVD (EAST LEG)</b>										
RT STA 3+707.351 (MAIN ST) TO 100+036.347			31							
RT STA 3+761.054 (MAIN ST) TO 100+035.233			43							
<b>RAMP J-3</b>										
LT STA 10+360.700 TO 2+454.738 (MAIN ST.)			7						2.3	
RT STA 10+361.500 TO 2+482.891 (MAIN ST.)			20						2.3	
<b>RAMP J-4</b>										
LT STA 2+464.420 (MAIN ST.) TO 10+024.000			7							
LT STA 10+024.000 TO 10+065.000		41								
RT STA 10+042.900 TO 2+494.939 (MAIN ST.)			34						2.0	
<b>TOTALS</b>		<b>* 41</b>	<b>* 368</b>	<b>* 3750</b>	<b>10</b>	<b>11</b>	<b>1346</b>	<b>156</b>	<b>12</b>	<b>* 7.6</b>
										<b>* 36</b>

\* NOT A TOTAL QUANTITY  
(FOR TOTAL QUANTITY ADD  
SIMILAR PAY ITEMS)

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 74 (I-74)  SCHEDULE OF QUANTITIES MAIN STREET RAMPS J-3 & J-4  DRAWN BY SRS CHECKED BY JJM
NAME	DATE	



DATE 12-20-04

C:\pbase\c:\pbase\101101\101101.dgn 12/21/2004 7:48:37 AM