

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	102
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*(90-11R-2;90(13,14)-1R-1

PAVING SCHEDULE

LOCATION	SUB GRAN MATL TYPE A (M TON)	SUB GRAN MATL TYPE B (M TON)	PCC BSE CSE 250MM (SO M)	PCC BSE CSE WID 250MM (SO M)	BIT MATLS PR CT (LITER)	AGG PR CT (M TON)	PCC PVMT 250MM JOINTED (SO M)	PVMT FABRIC (SO M)	STRIP REFL CRK CONT TREATMENT (METER)	PCC SHLDS 250MM (SO M)	AGG SUB-BASE (M TON)	BITUMINOUS CONC SUR CSE SUPERPAVE MIX D N70 (M TON)	BITUMINOUS CONC BIN CSE SUPERPAVE IL-19.0 N70 (M TON)	BITUMINOUS CONC BIN CSE SUPERPAVE IL-19.0L (LOW ESAL) 100mm (M TON)
MAIN STREET														
STA 2+402.933 TO 2+450.000	1323						1364							
STA 2+450.000 TO 2+600.000	4836						4085							
STA 2+600.000 TO 2+750.000	3637						3993							
STA 2+750.000 TO 2+900.000	1087	266	449	102	1430	8.0	1397	449	363			242	449	
STA 2+900.000 TO 3+050.000		342	670		2182	11.9		670	572			361	855	
STA 3+050.000 TO 3+200.000		419	860		1828	10.4		860	600			316	651	
STA 3+200.000 TO 3+350.000		478	1015		1736	10.2		1015	600			309	613	
STA 3+350.000 TO 3+500.000		490	1063		1763	10.4		1063	600			315	550	
STA 3+500.000 TO 3+650.000		549	1224		1995	11.8		1224	600			358	589	
STA 3+650.000 TO 3+800.000		449	945		2364	13.2		945	600			401	970	
STA 3+800.000 TO 3+950.000		514	1125		2010	11.7		1125	600			355	880	
STA 3+950.000 TO 4+100.000		472	851	179	1777	10.4		851	600			316	535	
STA 4+100.000 TO 4+162.000		124	20	202	565	3.1		20	208			96	167	
RAMP J-3														
STA 10+350.000 TO 10+371.000							198			40	218			1
RAMP J-4														
STA 10+017.000 TO 10+065.000							442			115	508			2
TOTALS	* 10883	* 4103	* 8222	* 483	* 17650	* 101.1	* 11479	* 8222	* 5343	* 155	* 726	* 3069	* 6259	3

SIDEROAD SCHEDULE

	SUB GRAN MATL TYPE A (M TON)	SUB GRAN MATL TYPE B (M TON)	PCC BSE CSE 250MM (SO M)	PCC BSE CSE WID 250MM (SO M)	BIT MATLS PR CT (LITER)	AGG PR CT (M TON)	PCC PVMT 250MM JOINTED (SO M)	INCIDENTAL BITUMINOUS SURFACING (M TON)	PVMT FABRIC (SO M)	STRIP REFL CRK CONT TREATMENT (METER)	BITUMINOUS CONC SUR CSE SUPERPAVE MIX D N70 (M TON)	BITUMINOUS CONC BIN CSE SUPERPAVE IL-19.0 N70 (M TON)
ALTORFER LANE AND FRONTAGE ROAD AT MAIN ST	868				11	0.4	1109	3				
NATIONAL STREET		207	534		160	1.6			534		49	64
CATERPILLAR TRAIL		41	97		29	0.3			97		9	12
BLACKJACK BOULEVARD (WEST LEG)		289	703	20	604	6.1			703	154	221	125
FRONTAGE ROAD		30		22	87	0.9				31	26	35
BLACKJACK BOULEVARD (EAST LEG)		189	499		150	1.5			499		45	60
TOTALS	* 868	* 756	* 1833	* 42	* 1041	* 10.8	* 1109	3	* 1833	* 185	* 350	* 296

* NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 74 (I-74)
 SCHEDULE OF QUANTITIES
 MAIN STREET
 RAMPS J-3 & J-4
 DRAWN BY SRS
 CHECKED BY JJM
 DATE 12-20-04



\\p1\eng-101\us\tempo\200404\200404.dwg