

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	103
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\*(90-III-R-2;90(I3,I4,I4-IR-1

**ENTRANCE SCHEDULE**

LOCATION	TYPE	WIDTH	PCC DRIVE PAVT 200MM (SQ M)	CCC&G B-15.60 (METER)
<b>MAIN STREET</b>				
RT STA 2+664.751	CE	10.70	95	16
RT STA 2+705.459	CE	7.40	34	8
RT STA 2+738.536	CE	9.00	39	8
RT STA 2+781.089	PE	4.00	19	8
RT STA 3+993.559	PE	3.60	18	8
RT STA 4+073.830	PE	7.20	44	9
RT STA 4+119.318	PE	5.40	37	12
<b>TOTALS</b>			<b>286</b>	<b>*69</b>

**ITEMS NOT OTHERWISE SCHEDULED**

ITEM	UNIT	QUANTITY
PROTECTIVE COAT	SQ.M	*18337
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	411

**SCHEDULE OF MISCELLANEOUS ITEMS**

LOCATION	SUB GRAN MATL TYPE B (M TON)	CONC HDWL FOR PIPE DRAINS (EACH)	PIPE UNDER DRAINS 150MM (METER)	SPBGR TYPE A (METER)	TRAFFIC BARRIER TERMINAL TYPE 2 (EACH)	
<b>MAIN STREET</b>						
LT STA 3+185.000 TO 3+255.000	555	1	7			
RT STA 3+185.000 TO 3+255.000	838	1	8			
RT STA 3+746.000 TO 3+794.000				49.53	2	
LT STA 3+970.000 TO 4+045.000	118		4			
RT STA 3+970.000 TO 4+045.000	142		5.5			
<b>TOTALS</b>		<b>*1653</b>	<b>*2</b>	<b>24.5</b>	<b>*49.53</b>	<b>*2</b>

**PATCHING SCHEDULE**

LOCATION	CLASS B TY 2 250MM (SQ M)	NUMBER OF PATCHES	WIDTH (M)	LENGTH (M)	D & G #35 TIE BARS (EACH)	DOWEL BARS 38MM (EACH)	SAW CUTS (METER)
<b>MAIN STREET</b>							
STA 3+657.394	37	1	20.5	1.8	68	68	42
STA 3+918.000	33	1	17.4	1.9	58	58	36
STA 4+100.000	11	1	7.9	1.4	26	26	16
<b>MISCELLANEOUS</b>							
<b>MAIN STREET (NB)</b>							
	330	51	3.6	1.8	510	510	367
	26	3	3.6	2.4	30	30	22
<b>MAIN STREET (SB)</b>							
	272	42	3.6	1.8	420	420	302
<b>TOTAL</b>		<b>*709</b>			<b>*1112</b>	<b>*1112</b>	<b>*785</b>

\* NOT A TOTAL QUANTITY (FOR TOTAL QUANTITY ADD SIMILAR PAY ITEMS)



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 74 (I-74)  
**SCHEDULE OF QUANTITIES**  
 MAIN STREET  
 RAMPS J-3 & J-4  
 DRAWN BY SRS  
 CHECKED BY JJM  
 DATE 12-20-04