

89201				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	107
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

• (90-11)R-2;90(13,14,14-1)R-1

### DRAINAGE REMOVAL ITEMS SUMMARY - MAIN STREET

LOCATIONS (STATION TO STATION)	CONCRETE HEADWALL REMOVAL EA	REMOVING INLETS EA	REMOVING MANHOLES EA	STORM SEWER REMOVAL				PIPE CULVERT REMOVAL		END SECTION REMOVAL EA
				300mm m	600mm m	750mm m	900mm m	LENGTH m	TYPE	
<b>MAIN STREET</b>										
2+442.600 -- 2+442.000				9.5						
2+658.174 -- 2+674.317								16.2	RCP	
2+733.525 -- 2+747.107								13.6	CMP	
2+749.395 -- 2+749.430						2.6				
2+849.191 -- 2+854.451								5.4	CMP	
2+883.930 -- 2+884.000					4.1					
3+416.921 -- 3+416.000					0.8					
3+658.000 -- 3+658.003					3.5					
3+680.000 -- 3+680.064							6.4			
4+111.979 -- 4+123.056								11.2	CMP	
<b>STATION AND OFFSET</b>										
2+442.680 12.712 RT		1								
2+442.000 22.656 RT	1									
2+748.504 14.621 RT										1
2+748.994 18.010 RT										1
2+749.450 19.029 LT										1
2+883.930 17.809 RT										1
2+983.000 15.000 RT										1
3+119.000 15.000 RT										1
3+186.311 12.311 RT										1
3+238.924 12.106 RT										1
3+416.921 12.063 RT										1
3+508.675 19.449 RT	1									
3+508.267 13.086 RT										1
3+570.418 13.860 RT										1
3+571.831 22.334 RT	1									
3+658.003 18.156 RT										1
3+657.880 23.974 LT	1									
3+682.000 15.000 RT			1							
3+762.937 18.079 RT										1
3+862.518 19.000 RT	1									
3+912.405 28.066 LT	1									
3+918.211 14.929 RT			1							
<b>TOTAL:</b>	<b>6 *</b>	<b>1 *</b>	<b>2</b>	<b>9.5</b>	<b>8.4 *</b>	<b>2.6</b>	<b>6.4</b>	<b>46.4</b>		<b>13 *</b>

\* = "NOT A TOTAL QUANTITY" (FOR TOTAL QUANTITY ADD SIMILAR ITEMS).

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SCHEDULE OF QUANTITIES</b> MAIN STREET RAMPS J-3 & J-4
DATE 12/20/04		DRAWN BY BRW CHECKED BY MJS

