

TOTAL BILL OF MATERIALS PLAN SET #2 (FOR INFORMATION ONLY)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	1701
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

* (90-111R-2)90(13,14,14-1)R-1

BILL OF MATERIALS			TOTAL QUANTITY	CONSTRUCTION TYPE AND SAFETY CODE	
CODE NO	ITEM	UNIT		INTERSTATE ROADWAY 2 LANE 1000-2A	ARTERIAL ROADWAY J000-2A
M4402530	PAVED SHOULDER REMOVAL	SQ M	6811	6811	
M4402600	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ M	342	342	
M4405000	PAVED DITCH REMOVAL	METER	757	757	
M4426250	CLASS B PATCHES, TYPE II, 375MM	SQ M	369		369
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	240		240
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	1364	1364	
M4820250	BITUMINOUS SHOULDERS 250MM	SQ M	570	570	
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250MM	SQ M	3422	3422	
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290MM	SQ M	4767	4767	
M5030300	CLASS MS CONCRETE	CU M	41.0	41.0	
M5080105	REINFORCEMENT BARS	KG	50	50	
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	3790	3790	
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	1	1	
M542E628	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 600MM	EACH	1	1	
M5422120	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 600MM	METER	39.0	39.0	
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	408.5	408.5	
M5500485	STORM SEWERS, CLASS A, TYPE 2 900MM	METER	38.5	38.5	
M5500495	STORM SEWERS, CLASS A, TYPE 2 1050MM	METER	15.0	15.0	
M5500515	STORM SEWERS, CLASS A, TYPE 2 1650MM	METER	45.5	45.5	
M5500875	STORM SEWERS, CLASS A, TYPE 3 750MM	METER	161.0	161.0	
M5510025	STORM SEWER REMOVAL 300MM	METER	11	11	
M5510035	STORM SEWER REMOVAL 375MM	METER	31	31	
M5510070	STORM SEWER REMOVAL 750MM	METER	39	39	
M5510105	STORM SEWER REMOVAL 1500MM	METER	1	1	
M5510110	STORM SEWER REMOVAL 1650MM	METER	2	2	
M6010125	PIPE DRAINS 300MM	METER	37.0	37.0	
M6010130	PIPE DRAINS 375MM	METER	10.5	10.5	
M6010135	PIPE DRAINS 450MM	METER	122.0	122.0	
M6010605	PIPE UNDERDRAINS 100MM	METER	2459.5	2459.5	
M6010610	PIPE UNDERDRAINS 150MM	METER	128.5	128.5	

Δ SFTY-3N

BILL OF MATERIALS			TOTAL QUANTITY	CONSTRUCTION TYPE AND SAFETY CODE	
CODE NO	ITEM	UNIT		INTERSTATE ROADWAY 2 LANE 1000-2A	ARTERIAL ROADWAY J000-2A
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	67.0	67.0	
M6010710	PIPE UNDERDRAINS 150MM (SPECIAL)	METER	2.0	2.0	
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
M6021485	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 37 GRATE	EACH	5	5	
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
M6023005	MANHOLES, SPECIAL, 1.2M DIAMETER	EACH	1	1	
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	17.2	17.2	
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	342.8	342.8	
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	419.0	50.2	368.8
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	562.0	88.0	474.0
M6062100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.15	METER	12.7	12.7	
M6062400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.60	METER	7.2	7.2	
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	787	23	764
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	218		218
M6066000	CORRUGATED MEDIAN	SQ M	57	6	51
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	198.12	198.12	
M6320030	GUARDRAIL REMOVAL	METER	284	284	
M6640120	CHAIN LINK FENCE, 1.8 METER	METER	29	29	
M6640650	CHAIN LINK GATES, 1.8M X 2.4M SINGLE	EACH	1.0	1.0	
M6641930	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	METER	187	187	
M7030100	SHORT- TERM PAVEMENT MARKING	METER	352.88		352.88
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	1367	1367	
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	3954	3954	
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	52	52	
M7030610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ M	9		9
M7030620	TEMPORARY PAINT PAVEMENT MARKING LINE 100MM	METER	98		98
M7030650	TEMPORARY PAINT PAVEMENT MARKING LINE 600MM	METER	21		21
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	35		35
M7040100	TEMPORARY CONCRETE BARRIER	METER	637	637	



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE (I-74)
TOTAL BILL OF MATERIALS -
PLAN SET #2, SHEET 2 OF 3
(FOR INFORMATION ONLY)

DRAWN BY
CHECKED BY

DATE 01/14/2005

01/14/2005 09:18:03 AM
D:\dftq\5589-74\dwg\cont\cont\11\eq0103-6a.dgn

CONTRACT 11: PLAN SET 2 OF 4 FINAL PLANS 01/05