

TOTAL BILL OF MATERIALS PLAN SET #2 (FOR INFORMATION ONLY)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	902
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		
* (90-11)R-2,90(13,14,14-1)R-1				

BILL OF MATERIALS			TOTAL QUANTITY	CONSTRUCTION TYPE AND SAFETY CODE		
CODE NO	ITEM	UNIT		INTERSTATE ROADWAY 2 LANE 1000-2A	ARTERIAL ROADWAY J000-2A	
M7040300	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	564	564		
M7210105	SIGN PANEL OVERLAY, SPECIAL	SQ M	33.10	33.10		
M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17		17	
M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	172.0		172.0	
M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	180		180	
M7800120	THERMOPLASTIC PAVEMENT MARKING - LINE 200MM	METER	160		160	
M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	21		21	
M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	21		21	
M7800600	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	7	7		
M7802010	POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM	METER	5557	5557		
M7802015	POLYUREA PAVEMENT MARKING TYPE I - LINE 150MM	METER	539	539		
M7802020	POLYUREA PAVEMENT MARKING TYPE I - LINE 200MM	METER	1314	1314		
M7802030	POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM	METER	174	174		
M7802060	POLYUREA PAVEMENT MARKING TYPE I - LINE 600MM	METER	12	12		
M7830100	PAVEMENT MARKING REMOVAL	SQ M	391	351	40	
M8100240	CONDUIT IN TRENCH, 30MM DIA., PVC	METER	5		5	
M8860100	DETECTOR LOOP, TYPE I	METER	49		49	
MX030217	PIPE CULVERT REMOVAL 375MM	METER	31.0	31.0		
MX030218	PIPE CULVERT REMOVAL 450MM	METER	44.0	44.0		
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	127	127		
MX032693	REMOVE TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	994	994		
MX033104	PIPE ELBOW 450MM	EACH	12	12		
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	551	551		
MX033183	SOIL STABILIZERS	KG	9450	9450		
MX033192	AGGREGATE SUBBASE	M TON	19945	19945		
MX033194	WHITEWASH	SQ M	21738	21738		
MX033447	PIPE CULVERT REMOVAL 600MM	METER	45	45		
MX033450	CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	CU M	44.7	44.7		
MX033460	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 100 MM	METER	342.0	342.0		
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	44	44		
MX406022	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	M TON	544		544	

Δ SFTY-3N

BILL OF MATERIALS			TOTAL QUANTITY	CONSTRUCTION TYPE AND SAFETY CODE		
CODE NO	ITEM	UNIT		INTERSTATE ROADWAY 2 LANE 1000-2A	ARTERIAL ROADWAY J000-2A	
MX406024	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	M TON	188	188		
MX406214	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	M TON	544		544	
MX406216	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	281	281		
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0L (LOW ESAL)	M TON	6629	6629		
MX704005	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	METER	106.75	106.75		
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	637	637		
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	28.1	28.1		
MX721010	COMPOSITE TEMPORARY SIGN OVERLAY	SQ M	13	13		
MZ012000	CONCRETE BARRIER BASE	SQ M	61	61		
MZ021500	EXPANSION JOINT 75MM	METER	74.8	74.8		
XX003278	CONCRETE COLLAR, CULVERT NO. 1	EACH	1	1		
X0323073	CLEAN EXISTING PAVEMENT EDGE JOINT	UNIT	6.3	6.3		
X0323677	STREET SWEEPING	HOUR	400	400		
X0323989	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY	EACH	11	11		
Z0007900	BUTT JOINTS	EACH	1	1		
Δ Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1		
Δ Z0030220	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Δ Z0050000	REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS	EACH	1	1		
Z0064540	SEEPAGE COLLAR	EACH	6	6		
*4001616	PAVED DITCH REMOVAL, SPECIAL	SQ M	380	380		
*4001617	PIPE CULVERT REMOVAL 300MM	METER	42	42		
*4001618	MANHOLES, TYPE A, 1.2M DIAMETER, FLAT SLAB TOP	EACH	1	1		



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE (I-74)
TOTAL BILL OF MATERIALS -
PLAN SET #2, SHEET 3 OF 3
(FOR INFORMATION ONLY)
DRAWN BY
CHECKED BY
DATE 01/14/2005

CONTRACT 11: PLAN SET 2 OF 4 FINAL PLANS 01/05

01/14/2005 09:48:03 AM
G:\dot\5589-74\dwg\contract\11\1103-6a.dgn

...:\dot\5589-74\dwg\contract\11\1103-6a.dgn 01/14/2005 09:48:03 AM