68201

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74*	**	TAZEWELL	1366	1182
STA. 99+830		TO STA. 99+850		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

*: WASHINGTON STREET
**:(90-1)DR-2;90(13,14,14-1)DR-1

VASCONCELLES
ENGINEERING CORP.
SPRINGFIELD, ILLINOIS

FINAL SURVEY NOTE BOOK | SURVEYED | PLOTTED | TYPED | AREAS | AREAS CHECKED | BY | DATE | NO.

ORIGINAL SURVEY NOTE BOOK | SURVEYED | PLOTTED | TYPED | AREAS | AREAS CHECKED | BY | DATE | NO.

ALL SEWER LINES DEEPER THAN 2.5 METERS ARE NOT SHOWN IN THESE SECTIONS

NOTE: FILL QUANTITY SHOWN IS FOR TOPSOIL EXCAVATION AND PLACEMENT PER CUBIC METER

SCALE
H 1: 100
V 1: 50

x60001-6bws

EXIST. R.O.W.

CUT = 0.0000 SQ m

FILL = 0.0880 SQ m

(PROJECTED E.O.P.)

143.022 | 143.162 | 143.253 | 143.105 | 143.050

2% | 2%

EXISTING 375 mm (15") STORM SEWER

EXISTING 300 mm (12") STORM SEWER

99+850.000

EXISTING PAVED DITCH

CUT = 0.0000 SQ m

FILL = 0.1840 SQ m

142.997 | 143.135 | 143.228 | 143.075 | 143.044

EXISTING RETAINING WALL

99+840.000

EXISTING 375 mm (15") STORM SEWER

CUT = 0.0000 SQ m

FILL = 0.0882 SQ m

142.973 | 143.111 | 143.210 | 143.186 | 143.045 | 142.999

EXISTING RETAINING WALL

99+830.000

EXISTING 375 mm (15") STORM SEWER

WASHINGTON STREET

CONTRACT 11: PLAN SET 2 OF 3 PRE-FINAL 02/02/04 VEC 40 OF 53. JOB NO. 751-001 VASCONCELLES ENGINEERING CORP. DESIGN FIRM REGISTRATION 184-002107