

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	.	TAZEWELL	1366	1198
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• (90-11R-2;9013, 14, 14-DR-1				

FOR INFORMATION ONLY

SET 3 - TOTAL BILL OF MATERIALS McCLUGGAGE BRIDGE TRAFFIC CONTROL PLAN LIGHTING, SIGNING AND ITS					IM		BRIDGE		URBAN		IM		CONSTRUCTION TYPE CODE				
					90% FED 10% STATE		80% FED 20% STATE				90% FED 10% STATE						
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	INTERSTATE ROADWAY 3 LANE (1) J000-2A	INTERSTATE ROADWAY 2 LANE (2) J000-2A	ARTERIAL ROADWAY (3) I000-2A	ARTERIAL ROADWAY (4) J000-2A	BRIDGE (5) X281-2A	BRIDGE (6) X581	BRIDGE (7) X281-2A	BRIDGE (8) X971-2A	RETAINING WALL (7) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	ITS Y035	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	14	1	3	5	5										
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	65	18	13	20	14										
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5			1	4										
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3		1	1	1										
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	2										2				
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1										1				
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1										1				
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	23	4	15	4											
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	23	4	15	4											
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	5										5				
78100300	REPLACEMENT REFLECTOR	EACH	79			79											
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2											2			
80500200	SERVICE INSTALLATION, TYPE B	EACH	1													1	
81400200	HEAVY-DUTY HANDHOLE	EACH	1													1	
81400400	CONCRETE HANDHOLE	EACH	1													1	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	12											12			
82500530	LIGHTING CONTROLLER TYPE CB-RCS 100AMP-240VOLT	EACH	1											1			
82500560	LIGHTING CONTROLLER TYPE CB-RCS 200AMP-480VOLT	EACH	1											1			
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1											1			
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	4											4			
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	16											16			
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	45											45			
84200800	POLE FOUNDATION, REMOVED	EACH	61											61			
M5020400	ROCK EXCAVATION FOR STRUCTURES	CU.M	14.3										6.6	7.7			
M5080105	REINFORCEMENT BARS	KG	1970	470	1170		330										

J:\proj\facts\data\3573\contract II\packaging\PS&E\Sheet For DSR\combined\Plans\Sheets\sp101-7.dwg 3:57:40 PM 12/22/2004

- (1) I -74 STA 152+445.837 TO STA 153+892.180
- (2) I -74 STA 153+892.180 TO STA 154+970.000
- (3) MAIN STREET STA. 2+800.000 TO STA. 4+157.000
CAMP STREET STA. 2+055.716 TO STA. 2+365.000 AND
CAMP STREET STA. 2+533.402 TO STA. 2+783.980
US 150-MCCLUGGAGE BRIDGE TCP
- (4) MAIN STREET STA. 2+015.141 TO STA. 2+310.000
MAIN STREET STA. 2+402.933 TO STA. 2+800.000
CAMP STREET STA. 2+365 TO STA. 2+533.402 AND
WASHINGTON STREET STA. 99+730.000 TO STA. 100+210.000

- SPECIALTY PROVISION REQUIRED
- △ SFTY-3N
- 5. BRIDGE PLANS SN 090-0160 (WB I-74 OVER MAIN STREET) AND
BRIDGE PLANS SN 090-0163 (WB I-74 OVER WASHINGTON STREET)
- 6. BRIDGE PLANS SN 090-0159 (WB OVER ALTORFER LANE AND TP&W RAILROAD)
- 7. BRIDGE PLANS SN 090-0156 (RAMP K-2 OVER MAIN STREET)
- 8. BRIDGE PLANS SN 090-0009 (WB I-74 OVER CAMP STREET, FARM CREEK AND
TP&W RAILROAD)
- 9. RETIANING WALL SN 090-8512 (ALONG RAMP J-3)
RETAINING WALL SN 090-8513 (ALONG RAMP K-2)

SET 3, SHEET 3 OF 5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SET 3
TOTAL BILL OF MATERIALS

DRAWN BY DJK
DATE: 12/21/04
DPA CHECKED BY DPA

ab **alfred benesch & company**
CONSULTING ENGINEERS
205 NORTH MICHIGAN AVENUE, CHICAGO, ILLINOIS 60601