



























LEGEND

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	•	TAZEWELL	1366	1213
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• (90-11)R-2; 90(13, 14, 14-1R-1				
CONTRACT NO. 68201				


-  PROPOSED HIGH MAST POLE: SEE SCHEDULE ON LIGHTING SHT. 5
-  PROPOSED HIGH MAST LUMINAIRE(S), DIRECTION OF ARROW INDICATES STREET SIDE: SEE SCHEDULE ON LIGHTING SHT. 5
-  B(B) PROPOSED STREET LIGHT UNIT: 13.5M ALUMINUM, TRANSFORMER BASE, 2.4M DAVIT ARM, 400W HPS, 240V MCIII LUMINAIRE. STAGE B.
-  B(C) PROPOSED STREET LIGHT UNIT: 13.5M ALUMINUM, TRANSFORMER BASE, 2.4M DAVIT ARM, 400W HPS, 240V MCIII LUMINAIRE. STAGE C.
-  C PROPOSED STREET LIGHT UNIT: 13.5M ALUMINUM, 1.8M DAVIT ARM, 400W HPS, 240V, MCIII LUMINAIRE.
-  F PROPOSED STREET LIGHT UNIT BY OTHERS: 13.5M MH, 400W HPS 240V LUMINAIRE ON COMBINATION TRAFFIC/ LIGHTING POLE
-  PROPOSED STREET LIGHTING CONTROLLER, CB-RCS, 100 OR 200 AMP, 240 OR 480 VOLT (AS NOTED): SEE LIGHTING SHT. 29
-  PROPOSED ELECTRICAL SERVICE INSTALLATION: SEE LIGHTING SHT. 28
-  PROPOSED JUNCTION BOX
-  CONDUIT BY OTHERS
-  PROPOSED EMBEDDED CONDUIT, 75mm PVC SCHEDULE 40, UNLESS OTHERWISE NOTED
-  PROPOSED ATTACHED CONDUIT, 25mm GALVANIZED
-  PROPOSED LIQUID-TIGHT FLEXIBLE CONDUIT, 25mm GALVANIZED
-  EMBEDDED CONCRETE INSERT (SEE DETAIL SHT. 33)
-  UNDERPASS LUMINAIRE, HPSV, S-C-1, 100WATT, 240VOLT (SEE DETAIL SHT. 33)
-  EXISTING HIGH MAST POLE
-  EXISTING LIGHTING CONTROLLER
-  EXISTING JUNCTION BOX
-  EXISTING ELECTRIC SERVICE INSTALLATION
-  EXISTING STREET LIGHT UNIT TO REMAIN
-  F EXISTING LUMINAIRE ON COMBINATION TRAFFIC/ LIGHTING POLE
-  X(A) EXISTING LIGHT UNIT TO BE REMOVED IN STAGE A
-  X(A) EXISTING TEMPORARY LIGHT UNIT TO BE REMOVED IN STAGE A.
-  EXISTING CONDUIT



PROPOSED ST. LT. CABLE IN CONDUIT



PROPOSED LT. TOWER CALL-OUT



PROPOSED CONDUIT CALL-OUT

LIGHTING SHEET 3 OF 41

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 ELECTRICAL LEGEND

ab alfred benesch & company
 CONSULTING ENGINEERS
 205 NORTH MICHIGAN AVENUE, CHICAGO, ILLINOIS 60601

DATE: 12/20/04
 DRAWN BY DJK
 CHECKED BY MKR

m:\proj\13573\lighting\4\contract\111100-7a_legend.dgn
 12/20/2004 12:44:06 PM