

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	TAZEWELL	1366	1252
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* (90-11)R-2;90(13,14,14-1)R-1		CONTRACT NO. 68201		

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TOTAL BILL OF MATERIALS
2 - 14	BILL OF MATERIALS - REGULATORY AND WARNING SIGNS
	BILL OF MATERIALS AND DETAIL DRAWINGS - GROUND MOUNTED SIGNS
15	-REMOVALS
16 - 17	-PROPOSED
18 - 19	-DETAIL DRAWINGS
20	BILL OF MATERIALS - OVERHEAD SIGNS
21 - 41	PERMANENT SIGNING PLAN
42 - 51	GUIDE SIGN PANEL DETAILS AND REGULATORY AND WARNING SIGN DETAILS
52 - 62	OVERHEAD SIGN STRUCTURES
63 - 72	CANTILEVER SIGN STRUCTURES
73	SOIL BORING LOGS
74	SIGN SUPPORT, PARAPET MOUNTED, TYPE 1

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STD. NUMBER	DESCRIPTION
720001	SIGN PANEL MOUNTING DETAILS
720006	SIGN PANEL ERECTION DETAILS
720011	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
720016	MAST ARM MOUNTED STREET NAME SIGNS
720021	SIGN PANELS, EXTRUDED ALUMINUM TYPE
729001	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

LIST OF I-74 PROJECT STANDARDS

STD. NUMBER	DESCRIPTION
733002-I74	SIGN SUPPORT, PARAPET MOUNTED, TYPE 1

DESCRIPTION	UNIT	TOTAL QUANTITY	BILL OF MATERIALS		
			REGULATORY AND WARNING SIGNS	GROUND MOUNTED GUIDE SIGNS	OVERHEAD GUIDE SIGNS
ROCK EXCAVATION FOR STRUCTURES	CU M	6.6			6.6
REINFORCEMENT BARS	KG	1970		1970	
SIGN PANEL - TYPE 1	SQ M	14	14		
SIGN PANEL - TYPE 2	SQ M	19	17	2	
SIGN PANEL - TYPE 3	SQ M	298		209	89
SIGN PANEL OVERLAY	SQ M	4		4	
STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	KG	8840		8840	
METAL POST - TYPE A	METER	8.5	8.5		
METAL POST - TYPE B	METER	8.0	8.0		
WOOD SIGN SUPPORT	METER	133.0	95.5	37.5	
OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-S (1.22M X 1.37M)	METER	23.0			23.0
CONCRETE FOUNDATIONS	CU M	33.4		33.4	
DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	31.6			31.6
OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-S (0.90M X 1.68M)	METER	9.0			9.0
SIGN SUPPORT, PARAPET MOUNTED, TYPE 1	EACH	2	2		
REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	14	14		
REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	65	55	10	
RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	5		
RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	2	1	
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	2			2
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1			1
REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1			1
REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	23		23	
REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	23		23	
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	5			5

SIGNING SHEET 1 OF 74

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SIGNING PLAN INDEX OF SHEETS AND TOTAL BILL OF MATERIALS</p> <p>SCALE 1:500                      DRAWN BY MEG DATE 12/22/2004                      CHECKED BY BCG</p>



I:\projects\dot\11\1101-74\1101-74.dgn 12/22/2004