

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74		TAZEWELL	1366	1377
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BILL OF MATERIALS FOR PLAN SET #4
FOR INFORMATION ONLY

				URBAN / IM										90% FED 5% STATE 5% CITY				90% FED 10% CITY			
				CONSTRUCTION TYPE CODE																	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE X271-2A	BRIDGE X281-2A	BRIDGE X761-2A	BRIDGE X028-2A	MINOR STRUCTURES Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F		
+ 63100167	TRAFFIC BARRIER TERMINAL, TYPE I SPECIAL (TANGENT)	EACH	5	5																	
76100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	229	229																	
+ 78201000	TERMINAL MARKER DIRECT APPLIED	EACH	5	5																	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	229	229																	
86301000	TERMINAL FACILITY	EACH	1	1																	
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M. TON	25.6	25.6																	
M4060300	AGGREGATE (PRIME COAT)	M. TON	135.9	135.9																	
M4060990	TEMPORARY RAMPS	SQ. M	226	226																	
M4400040	BITUMINOUS SURFACE REMOVAL, 40 MM	SQ. M	39,807	39,807																	
M4401000	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. M	3,625	3,625																	
M4426250	CLASS B PATCHES, TYPE II, 375 MM	SQ. M	1,122	1,122																	
M4429400	SAW CUTS	METER	2,359	2,359																	
M4812000	AGGREGATE SHOULDERS, TYPE B	M. TON	1,207	1,207																	
M4820000	BITUMINOUS SHOULDERS	M. TON	3,289	3,289																	
+ M6320030	GUARDRAIL REMOVAL	METER	57	57																	
M6330610	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	METER	1,291	1,291																	
M7030100	SHORT TERM PAVEMENT MARKING	METER	2,849	2,849																	
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100 MM	METER	11,201	11,201																	
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150 MM	METER	1,400	1,400																	
M7030250	TEMPORARY PAVEMENT MARKING - LINE 200 MM	METER	527	527																	
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. M	87	87																	
M7802010	POLYUREA PAVEMENT MARKING, TYPE I - LINE 100 MM	METER	11,201	11,201																	
M7802015	POLYUREA PAVEMENT MARKING, TYPE I - LINE 150 MM	METER	1,400	1,400																	
M7802020	POLYUREA PAVEMENT MARKING, TYPE I - LINE 200 MM	METER	527	527																	
M7802030	POLYUREA PAVEMENT MARKING, TYPE I - LINE 300 MM	METER	50	50																	
M8100240	CONDUIT IN TRENCH, 30 MM DIA., PVC	METER	28.2	28.2																	
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	23.7	23.7																	
M8150205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	METER	8.4	8.4																	
M8731510	ELECTRIC CABLE IN CONDUIT, LEAD IN, NO. 18, 3 PAIR	METER	33.6	33.6																	
M8860400	DETECTOR LOOP SPECIAL	METER	45.7	45.7																	
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M. TON	223	223																	
MX406066	POLYMERIZED BIT. CONCRETE SURFACE COURSE, SUPERPAVE, MIX E N90, 38mm	M. TON	3,905	3,905																	
MX406248	POLYMERIZED BIT. CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0 N90, 57mm	M. TON	5,845	5,845																	
MZ017205	DOWEL BARS 38 MM	EACH	3,180	3,180																	
MZ021500	EXPANSION JOINTS 75 MM	METER	44	44																	
X6330100	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE I SPECIAL	EACH	4	4																	
*4001603	BITUMINOUS SURFACE REMOVAL - BUTT JOINT (SPECIAL)	SQ. M	1,571	1,571																	
*4001614	CLASS B PATCHES (SPECIAL)	SQ. M	107.2	107.2																	

* SPECIALTY ITEMS
+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
Δ NON PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BILL OF MATERIALS
FAI ROUTE 74 (I-74)
DATE 12/13/04
DRAWN BY CEM
CHECKED BY CEM