

SUMMARY OF QUANTITIES (Cont'd)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325	501	COLES	26	4

CONTRACT NO. 70415

<u>CODE NO</u>	<u>ITEM</u>	<u>CONSTRUCTION TYPE CODE:</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>LOCATION OF WORK:</u>	<u>FAP 325 IL. 16 & 6TH ST. 90% FED. 10% STATE</u>	<u>FAP 325 IL. 16 & 6TH ST. 90% FED. 5% STATE 5% CITY</u>	<u>FAP 325 IL. 16 & LOGAN ST. 90% FED. 5% STATE 5% CITY</u>	<u>FAP 325 IL. 16 & LERN RD. 90% FED. 10% STATE</u>	<u>FAP 325 IL. 16 & LERN RD. 100% CITY</u>
						1000-1A	Y031 - 1F	Y031 - 1F	Y031 - 1F	Y030 - 1E
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC		FOOT	28.0			28.0			
81012800	CONDUIT IN TRENCH, 3" DIA., PVC		FOOT	88.0			29.0	32.0	27.0	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC		FOOT	77.0			44.0		33.0	
81013100	CONDUIT IN TRENCH, 5" DIA., PVC		FOOT	75.0					75.0	
81013200	CONDUIT IN TRENCH, 6" DIA., PVC		FOOT	4.0			4.0			
81021550	CONDUIT, AUGERED 2" DIA., PVC		FOOT	82.0					82.0	
81021570	CONDUIT, AUGERED 3" DIA., PVC		FOOT	551.0			173.0	179.0	199.0	
81021590	CONDUIT, AUGERED 4" DIA., PVC		FOOT	185.0			59.0		126.0	
81030100	CONDUIT SPLICE		EACH	2.0			1.0	1.0		
81400100	HANDHOLE		EACH	15.0			7.0	2.0	6.0	
81400300	DOUBLE HANDHOLE		EACH	2.0			1.0		1.0	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	1,690.0			359.0	219.0	1,112.0	
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10		FOOT	1,961.0						1,961.0
82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT		EACH	4.0						4.0
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET		EACH	2.0			1.0		1.0	
86600010	GULFBOX JUNCTION		EACH	4.0					4.0	
86600020	GULFBOX JUNCTION REMOVAL		EACH	6.0					6.0	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C		FOOT	593.0			593.0			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C		FOOT	4,338.0			631.0	771.0	2,936.0	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C		FOOT	3,792.0			2,076.0	522.0	1,194.0	
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR		FOOT	6,355.0			1,833.0	1,073.0	3,449.0	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C		FOOT	44.0			20.0		24.0	
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.		EACH	3.0				1.0	2.0	
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.		EACH	3.0				1.0	2.0	
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.		EACH	4.0			4.0			
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.		EACH	1.0			1.0			
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.		EACH	1.0			1.0			
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.		EACH	1.0			1.0			