

6TH STREET SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325	501	COLES	26	10

CONTRACT NO. 70415

TREE REMOVAL OVER 15

<u>LOCATION</u>	<u>UNIT</u>
STA. 97+33; 29.3' RT.	16 UNIT

SODDING, SALT TOLERANT

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SQ. YD.</u>
96+49 RT.		97+10 RT.	33
97+11 RT.		97+68.5 RT.	36
98+14.5 RT.		99+36 RT.	25
TOTAL =			94 SQ. YD.

PCC DRIVEWAY PAVT 6

<u>LOCATION</u>	<u>SQ. YD.</u>
RT. 97+97	23 SQ. YD.

PC CONCRETE SIDEWALK 5

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SQ. FT.</u>
RT. 97+10		RT. 97+15.5	69
RT. 99+24		RT. 99+52	85
TOTAL =			154 SQ. FT.

PAVEMENT REMOVAL

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SQ. YD.</u>
98+10.5; 14.2' R		99+70.0; 42.0' R	55 SQ. YD.

DRIVE PAVEMENT REMOVAL

<u>LOCATION</u>	<u>SQ. YD.</u>
RT. 97+97	62 SQ. YD.

COMB CURB & GUTTER REM

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>FOOT</u>
RT. 96+56		RT. 99+57	348 FOOT

SIDEWALK REMOVAL

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SQ. FT.</u>
RT. 97+02.3		RT. 97+23.7	134
RT. 99+29.2		RT. 99+32.0	150
TOTAL =			284 SQ. FT.

SS 1 RCP CL 4 12

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>FOOT</u>
35+03.5; 36.5' L		35+13.7; 38.0' R	10 FOOT

INLETS TA T3F&G

<u>LOCATION</u>	<u>EACH</u>
STA. 35+13.7; 38.0' RT.	1 EACH

MAN ADJ NEW TIF CL

<u>LOCATION</u>	<u>EACH</u>
STA. 98+33; 24.2' RT.	1 EACH

REMOVE CB - MAINTAIN FLOW

<u>LOCATION</u>	<u>EACH</u>
STA. 35+06.2; 36' RT.	1 EACH

THPL PVT MK LINE 4

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>FOOT</u>	
CL 96+52.3		CL 98+15.5	164	YELLOW
CL 98+15.5		98+75.8; 6' LT.	120	DBL YELLOW
98+75.8; 6' LT.		99+43.8; 6' LT.	136	DBL YELLOW
98+75.8; 6' RT.		99+43.8; 6' RT.	69	WHITE
98+20.6; 18' RT.		99+43.8; 18' RT.	124	WHITE
TOTAL =			613 FOOT	

THPL PVT MK LTR & SYM

<u>LOCATION</u>	<u>SQ. FT.</u>
98+20.5 RT TURN LANE	15.6
98+73.5 RT TURN LANE	15.6
98+75.0 LT TURN LANE	15.6
99+22.5 LT TURN LANE	15.6
99+22.5 RT TURN LANE	15.6
TOTAL = 78 SQ. FT.	

THPL PVT MRK LINE 6

<u>LOCATION</u>	<u>FOOT</u>
SOUTH CROSS WALK	125
EAST CROSS WALK	170
TOTAL = 295 FOOT	

THPL PVT MRK LINE 24

<u>LOCATION</u>	<u>FOOT</u>
SOUTH LEG STOP BAR	38 FOOT

PAVT MARKING REMOVAL

<u>LOCATION</u>	<u>SQ. FT.</u>
EAST CROSSWALK	45
SOUTH CROSSWALK	11
SOUTH STOP BAR	28
TOTAL = 84 SQ. FT.	

REMOVE EXIST HANDHOLE

<u>LOCATION</u>	<u>EACH</u>
34+21.9; 45.6' RT.	1
34+35.1; 52.1' RT.	1
34+34.5; 60.0' LT.	1
34+94.9; 53.9' LT.	1
35+27.3; 36.9' LT.	1
35+16.0; 40.2' RT.	1
98+27.9; 23.5' RT.	1
101+70.1; 24.5' LT.	1
TOTAL = 8 EACH	

REMOVE EXIST CONC FOUNDATION

<u>LOCATION</u>	<u>EACH</u>
34+23.5; 42.8' RT.	1
34+31.2; 52.2' RT.	1
34+14.6; 41.3' LT.	1
34+26.2; 42.6' LT.	1
34+36.9; 64.6' LT.	1
34+94.4; 60.8' LT.	1
34+95.7; 56.9' LT.	1
35+11.9; 42.1' LT.	1
34+95.1; 53.6' RT.	1
35+06.3; 43.3' RT.	1
TOTAL = 10 EACH	

HANDHOLE

<u>LOCATION</u>	<u>EACH</u>
34+24.0; 43.0' LT.	1
34+37.5; 54.8' LT.	1
34+99.0; 71.0' RT.	1
35+17.3; 45.5' RT.	1
34+14.3; 43.0' RT.	1
34+29.5; 56.0' RT.	1
35+18.0; 43.7' LT.	1
TOTAL = 7 EACH	

CONC FOUNDATION TY A

<u>LOCATION</u>	<u>FOOT</u>
34+24.5; 44.0' RT.	3.1
34+34.5; 54.0' LT.	3.1
35+04.3; 56.5' RT.	3.1
35+09.5; 42.5' LT.	3.1
TOTAL = 12.4 FOOT	

TS POST A 16

<u>LOCATION</u>	<u>FOOT</u>
34+24.5; 44.0' RT.	1
34+34.5; 54.0' LT.	1
35+04.3; 56.5' RT.	1
35+09.5; 42.5' LT.	1
TOTAL = 4 FOOT	

CONC FOUNDATION TY D

<u>LOCATION</u>	<u>FOOT</u>
34+95.8; 68.0' LT.	3.5 FOOT

CONC FOUNDATION TY E

<u>LOCATION</u>	<u>FOOT</u>
34+10.0; 42.5' LT.	11
34+30.5; 60.2' RT.	10
34+95.8; 68.0' LT.	10
35+33.0; 38.5' RT.	11
TOTAL = 42 FOOT	