

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	*	MOULTRIE	14	3

CONTRACT NO. 70460  
\* D-5 CONTRACT MAINT 2005-12

LOCATION OF WORK:

FAP 762 (IL 32)  
STA. 207+00  
TO  
STA. 271+00  
100% STATE  
TWO-LANE RURAL

CONSTRUCTION TYPE CODE:

1000  
TOTAL  
QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,534.0
40600300	AGGREGATE (PRIME COAT)	TON	31.0
40600990	TEMPORARY RAMP	SQ YD	320.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2	SQ YD	15,337.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	90.8
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT TERM PAVT MARKING	FEET	1050.0
70301000	WORK ZONE PAVT MARKING REM	SQ FT	175.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4	FOOT	14,400.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	72.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	72.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX ""C"", N50	TON	1,288.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	868.0
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	219.0

\*SPECIALTY ITEMS