

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	*	MOULTRIE	11	7

CONTRACT NO. 70460
• D-5 CONTRACT MAINT 2005-12

PARTIAL DEPTH PATCHING (Cont.)

STATION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL X4401705	BIT MIX FOR PATCHING Z0004800
				(sq. yd)	(Ton)
257+02	NB	4	12	5.3	1.3
257+35	NB	6	12	8.0	2.0
257+63	NB	8	12	10.7	2.7
258+00	NB	4	12	5.3	1.3
258+36	NB	8	12	10.7	2.7
260+27	NB	8	12	10.7	2.7
260+57	NB	4	12	5.3	1.3
260+76	NB	6	12	8.0	2.0
261+39	NB	10	12	13.3	3.4
261+65	NB	10	12	13.3	3.4
263+59	NB	4	12	5.3	1.3
265+47	NB	10	12	13.3	3.4
265+74	NB	6	12	8.0	2.0
265+89	NB	6	12	8.0	2.0
265+96	NB	15	12	20.0	5.0
266+26	NB	8	12	10.7	2.7
268+62	NB	4	12	5.3	1.3
269+49	NB	4	12	5.3	1.3
NB TOTALS				486.7	122.6
217+52	SB	4	12	5.3	1.3
217+75	SB	4	12	5.3	1.3
220+35	SB	4	12	5.3	1.3
221+72	SB	4	12	5.3	1.3
225+74	SB	4	12	5.3	1.3
226+10	SB	4	12	5.3	1.3
230+60	SB	4	12	5.3	1.3
231+53	SB	4	12	5.3	1.3
231+68	SB	4	12	5.3	1.3
231+88	SB	4	12	5.3	1.3
232+08	SB	4	12	5.3	1.3
239+10	SB	4	12	5.3	1.3
240+55	SB	4	12	5.3	1.3
241+08	SB	8	12	10.7	2.7
241+55	SB	4	12	5.3	1.3
242+06	SB	4	12	5.3	1.3
242+46	SB	4	12	5.3	1.3
243+04	SB	8	12	10.7	2.7